

P. No 149  
2020-21

*[Handwritten signature]*

OFFICE OF THE EXECUTIVE ENGINEER SPECIAL PHE DIVISION KULGAM

Ashaq Hussain Itoo  
(tractor)  
Gh. Mohd Itoo R/o Mohdpora  
d.No:73/Aay/SE/Hyd/Ang/2004-05  
Advt. 27.54 lacs

ORDER No: 06/021  
Date: 04/021

No/PHE/WK

504-05

Dated: 04/021

29-4-021

Alloted cost: 2738056.00

Subject: Retrofitting of Water Supply Scheme Kutbani by way of providing and laying of pipes for providing new sub-main and dist. Lines to village Kutbani and replacing some deteriorated pipes of sub-main lines feeding Naid Hanjen including maintenance for a period of three years which includes D.I.P of 12 months (J.J.M).

Ref: Your tender received in response to this office E-NIT No : 65/PHEK/ of 2020-21 Issued under No: PHK/5220-30 Dated:05-03-2021

For and on behalf of president of India contract for the above noted work is hereby fixed with you on the following alloted rates:

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Alloted Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 min width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:	1038.86	cum	420	436321.2
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. Layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering lead upto 50m and lift upto 1.5	934.97	cum	200	186994
3	P/L of GI pipes complete with GI fittings excl the trenching and refilling etc ( external work) light class pipes 80mm dia pipe	775.00	Mtr	774	599850
3.1	65mm dia GI pipe	1700.00	mtr	628	1067600
3.2	50mm dia GI pipe	200.00	mtr	477	95400
3.3	40mm dia GI pipe	300.00	mtr	386	115800
3.4	25mm dia GI pipe	450.00	mtr	249	112050
3.5	20mm dia GI pipe	450.00	mtr	182	81900
3.6	15mm dia GI pipe	253.00	mtr	144	36432
4	Extra carriage of materials from dumping site to actual site of work by manual means for an average lead of 500mtrs	18.474	M.T	309	5708.466
<b>Total::</b>					<b>2738055.67</b>

Terms and conditions:

- The cost of work should in no case exceed beyond 2738056/= (Rupees twenty seven lac thirty eight thousand fifty six only)
- The date of start shall be reckoned three days from the date of issue of allotment.
- the total value shall be imposed upon you.
- Earnest money deposited by you vide CDR No: 22333848 Dated. 16-04-2021 Rs 82700/= shall be released only after successful completion of the work and expiry of defect clause
- You have to attend the Divisional office with enlistment card for drawal of agreement within three days from the date of issuance of this allotment order. However non -drawal of agreement will not prevent the contract from being enforced upon you.
- All other terms and conditions shall remain the same as laid down in the original NIT /PWD Form No.25 double & FC -33

*[Handwritten signature]*  
H.D.

*[Handwritten signature]*  
Executive Engineer  
Special PHE Division Kulgam

Copy to the::::

- Asstt. Ex. Engineer PHE Sub-Division Kulgam/D Hpora for information and necessary action. He will ensure the completion of work within stipulated time period & strictly in accordance with approved proposals, besides the amount of work does not exceed by the provision of allotment in any case for which he shall be personally responsible.
- AAO Divisional office for Informalton
- Divisional drawing branch for Informalton

*[Large handwritten signature]*

OFFICE OF THE EXECUTIVE ENGINEER SPECIAL PHE JAL SHAKTI DIVISION KULGAM

M/S - Ashaq Hussain Khan(contractor)  
S/c Mohd Maqbool Khan  
R/o DK Marg  
Regd No SE-II/UEED/BEE/110/2021-22  
PAN No. FQCPK2299Q

No:- PHE/Wks/ 8407-09  
Dated: 07-02-2023

GST No: 01FQCPK2299Q1ZD

Allotment order No 125 of 2023  
Dated. 07.02.2023

Name of work-Laying/ Fitting of pipes for water supply scheme Vovrikhull Incl. installation of FHTCs under JJM programme  
Ref:- This office e-NIT No:11 /PHEK issued under No.636-52 Date: 04-05-2022, District dev. Commissioner Kulgam's authorisation No:350/DCK of 2022 dated 06/08/2022 issued under No-DDCK/JJM/2022-23/3674-77 Dated. 06-08-2022, Superintending Engineer Hydraulic Circle Anantnag's order no:SE/Hyd/Cars/4737-38 dated. 11-08-2022 & This office LOI No:PHK/3327-31 Dated.17-08-2022

Accord of Administrative No and date	48/DB/SE of 2022 dated. 08-07-2022
Technical sanction No and date:	191/SE/DB of 2022 Dated. 22-08-2022
Advertised amount of work	Rs 22.91 lacs
Alloted amount of work	Rs 2117311.00
<b>Rupees Twenty One Lakh Seventeen Thousand Three Hundred and Eleven</b>	

For and on behalf of Lt.Governor of UT of J&K, the contract for the above work is hereby fixed with you on the following rates quoted/accepted by you on the terms and conditions given as under:

SLNo	Bidder Name	Quoted Percentage	Quoted amount in figures and words		
1.00	Ashaq Hussain Khan(contractor)	-7.600	2117311.167	Twenty One Lakh Seventeen Thousand Three Hundred and Eleven	
DESCRIPTION OF ITEMS OF AS PER BOQ					
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides andramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: all kinds of soil	1742.400	Cum	436	758686.400
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	1568.160	Cum	198.7	311593.392
3	Supply and filling of filter media from approved source - Gravel (Graded gravel - size ranging from 2.0mm to 40.00 mm) in filter beds. (including all carriages, complete job)	6.000	Cum	7700	46200.000
4	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work. 15 to 40mm dia GI pipe	4770.000	m	20.25	96592.500
5	25 mm and 32 mm dia. G.I. pipes	2000.000	m	30.65	61300.000
6	40 mm and 50 mm dia. G.I. pipes	4000.000	m	40.8	163200.000
7	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete 25 to 400mm	45.000	each	666.25	29981.250
8	50 to 80 mm nominal bore	5.000	each	1268.25	6341.250
9	Providing and laying D.I. standard specials such as tees, bends, collars, tapers, caps etc. suitable for flanged jointing as per IS : 9523 (as per site requirement) 15mm nominal bore	35.000	each	318.85	11159.750
10	Carriage of G.I./D.I pipes below 100mm dia from Stocking yard to the dumping site by mechanical means 5kms	24.000	Ton	183.356	4400.544
11	Beyond 5 km upto 10 km per km	24.000	Ton	13.26	318.240
12	Beyond 10 km upto 20 km per km	24.000	Ton	10.799	259.176
13	Beyond 20 km per additional km	24.000	Ton	8.832	211.968
14	Carriage of G.I./D.I pipes below 100mm dia from dumping site to actual site of work by manual means lat 50m	24.000	Ton	153.249	3677.976
15	Beyond 1st 50m	24.000	Ton	27.494	539.856
16	Restoration of road berm along pipe alignment to be damaged	200.000	m	480	96000.000
17	Restoration of W.B.M Road at spots	20.000	m	1000	20000.000
18	P/F of 3HP Backwash motor with all allied components (comp. job)	1.000	job	80000	80000.000
19	Installation of 15kw DG Set complete including cost of C.G. T Shed for DG SET (comp.job)	1.000	job	600000	600000.000
Grand Total:::					2291462.302
<b>Total alloted cost after deduction of -7.60% below as per the quoted rates of contractor:</b>					<b>2117311.000</b>

Terms and conditions:::

1	The alloted cost of the work is Rs2117311.00 (Rupees twenty one lac seventeen thousand three hundred eleven only).However the alloted cost should in no case exceed beyond DAP/DPR.
2	The date of start shall be reckoned from the date as mentioned in the LOI/allotment.
3	The work shall have to be completed within a period of (90) days from the date of issuance of this allotment order, failing which penalty upto 10% of the total value shall be imposed upon you.
4	Earnest money deposited by you Vide CDR/BG/FDR No3112195 Dated24/08/2022 For Rs64519.00 shall be released only after the successful completion of work and after the expiry of defect clause.
5	The date of start of work shall be reckoned within one week from the date of issuance of this Contract allotment
6	The work shall have to be completed within a period of ninety (90) days from the date of issuance of allotment mentioned above

7	After testing and commissioning of work the bidder will have to make a trial run of the work for a period of 03 months during which the bidder will have to operate and maintain the executed work to the full satisfaction of the Department. the DLP. In case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time as deemed fit for getting the defect rectified subject to maximum ceiling of 06 months
8	The defects Liability period shall be for a period of 12 Months which shall commence after the successful completion of Trial run The bidder shall be responsible to make good & remedy at his own expense any defect in works which is noticed during the DLP in case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time The bidder shall be responsible for the time and proper setting out of all the works and for the correctness of the positions levels dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in as deemed for getting the defect rectified subject to a maximum ceiling of 6 Months
9	The rates are including the Charges for Submission of progress Geo-tagged photographs, vedigraphic record through the professional person before during & after construction and progress reports in both hard and soft copies Taking Cross-Sections L Sections by Auto Level/ETS before and after execution Preparation of work abstract of executed work, preparation of bills besides the rates quoted/alloted are inclusive of taxes and the fees viz GST/income tax/Cess etc shall be deducted at source from running account bills.
10	All the Cement RCC Steel plumbing and other works shall be strictly as per relevant IS Codes CPHEEO norms/requirements/specifications and normal PWD precautions
11	You shall be solely responsible for carrying out the mandatory tests required or as decided by Engineer-in-charge for the quality control at your own costs. The cost of conducting all tests shall be done by the contractor and shall be deemed to have been included in the term rates for various items of work and percentage rate tendered Nothing extra shall be payable on this account
12	You have to furnish the confirmatory survey, structural & functional design including geo-technical analysis, soil investigation and quality control tests done at your level duly vetted by DIGC as per terms & conditions of the NIT The vetting charges for the design if any are to be done by you
13	The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, quality of materials used for construction and quality of machinery nated in each scheme The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluation of the performance of the Contract during the Contract Period
14	The provisional/lumpsum shall be executed as per the site conditions and specifications of CPWD/manual. Besides any item of work not included in the BOQ but required for the completion of the work, shall be executed by the contractor, as directed by the Department Such extra item shall be paid at J&K SSR 2020 rates with allotted appreciation /Deprisation of the contractor in case such item does not figure in J&K SSR 2020, the same shall be paid as per the current market rate analysis, to be approved by the competent authority
15	No price escalation will be paid for completion of the work within stipulated time or extended data of completion due to any reason whatsoever
16	No extra claim towards any type of tax, freight etc shall be entertained whatsoever.
17	No mobilisation advance shall be paid
18	Retention money/Security deposit shall be 10% of the contract value. The Security Deposit is to be recovered at the rate of 10% of bi amount from Running Account Bills and shall be released after completion of the defect liability period
19	In the event of allottee falling, declining, neglecting or delaying the supplies/works or in the event of any damage securing or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the timebeing enforce in the UT
20	All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract are the responsibility of the Bidder.
21	Any failure or commission to carry out the provision of the contract shall not give any claim by the department or bidder one against the other if such failure of commission occurs by the ACT OF GOD which shall include all natural calamities such as fires floods earthquake, hurricane, strikes, riots, embargoes or from any political or other reasons beyond the control of the parties including war, or a state of insurgency
22	The bidder shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc
23	From the commencement of the work to the completion thereof the same shall be under the bidders charge The bidder shall be held responsible for and make good any loss or injuries by fire or other causes/theft and shall hold the Government harmless for any claims for injuries to persons or damage a property happening from any neglect, default, want of proper care and misconduct on the part of the bidder, or any of his employees during the execution of work. The bidder shall be responsible for the compensation if any, to labour under the existing labour laws of the country
24	In the event of the death or insanity or insolvency or imprisonment of the bidder or where the bidder being a partnership or firm becomes dissolved or being corporation goes into liquidation, voluntary or otherwise, the contract may, in the option of the Engineer in charge be terminated by notice in writing posted at the site of the works
25	The damage caused to the work during execution or prior to actual completion of workhanding over of the project before defect liability period due to any natural calamity human interference, the same shall be got restored and made good by you at your own cost
26	No damage is caused to existing structures like roads, bridges, buildings or other public utilites as a result of construction of this work .Where ever any damage occurs to any public/private infrastructure or public utility, the same shall be rectified/made good by you at your own cost

27	Adequate precautions be taken for environment and social protection besides, all safety practices in vogue be strictly adhered to during execution of work
28	No objection certificate from the concerned regulatory authority may also be sought whenever required
29	All other terms & conditions will remain same as laid down in the original NIT SBD GPR-2017/ Procurement Manual 2019/Operational guidelines for JJM
30	The back filling Item shall not be paid if the road berm damaged is restored by way of filling extra quantity of WBM at site. Item No 16 & 17 shall not be paid with back filling item

*[Handwritten signature]*

*[Handwritten signature]*  
 Executive Engineer  
 PHE JSD Kulgam

Copy to the  
 Superintending Engineer Hydraulic Circle Aantnag for favour of information  
 Asstt. Ex. Engineer PHE Sub-Division Kulgam for information  
 AAO Divisional office for information