OFFICE OF THE EXECUTIVE ENGINEER SPECIAL PHE JAL SHAKTI DIVISION KULGAM

M/s Khurshid Ahmad Mir Ab Aziz Mir Reshinagar 222/A/CE/KCC/PDC of 1997-98 AIFPM2693C

No:- PHE/Wks/ 2465-67 Dated:::: 7/0/2023 45

Name of work: Construction 0.30lac Gallons SR, 0.25Lac Gallons SR, 0.10 Lac Gallons SR, Chain Link fencing,
Approach Road and allied works WSS Sekjan (JJM)

Ref:- This office e-NIT No.58 PHEK issued under No.:PHEK/7149-63Date: 14/12/2022 This office LOI No 9591-95 Dated 31/03/2023 Superintending Engineer Hydraulic Cirle Anantnag's Authorization letter No SE/Hyd/Cors/13796 dated 27/03/2023:

	CE/PHE/DB/351 of 2023 Dt 23/02/2023
Accord of Administrative No and date	CE/PHE/DB/872 of 2023 Dt 27/02/2023
Technical sanction No and date:	R\$125.98 lacs
Advertised amount of work	Rs109.20 lacs
Alloted amount of work	
Rupees One Crore Nine lacs twenty thousands only	
	and the following

For and on behalf of LLGoverner of UT of J&K, the contract for the above work is hereby fixed with you on the following rates

quoted/accepted by you on the terms and conditions given as under:

Quoted /negotiated /ne

			Rate		
	1 M/s Khurshid Ahmad Mir	4.00	Re109.20 lacs	Rupees One Crore I thousand	Nine lacs twenty s only
	DESCRIPTION OF ITEMS	S AS PER BO	Q	The second	N P VS
S.No	Description of items	Quantity	Unit	Estimates rute	Total
1	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material all kinds of soil	325.30	Cum	81.65	26560.91
2	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.all kinds of soil (80% All Kinds of soils)	1294.00	Cum	539.35	697918.90
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	517.00	Cum	198.70	102727.90
4	Providing and laying hand packed stone soling 50 mm nominal size including filling, spreading, dressing, ramming, all leads lifts and all carriages complete.	140.57	Cum	1320.00	185555.04
5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size)	130.00	Cum	6434.01	836421.30
6	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	68.35	Cum	4861.84	332306.42

7 8	roviding and laying in position specified grade of einforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:11/2:31 cement: 11/2 coarse sand: 3 graded stone aggregate 20 mm nominal size)	100.00	Cum	7800.76	780076.00
8	Reinforced cement concrete work in walls (any hickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	125.46	Cum	9408.14	1180363.43
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with:	21.40	Cum	9849.35	210795.68
10	Reinforced cement concrete work in arches, arch ribs, domes, vaults shells, folded plate and roofs having slope more than 15° upto floor five level level including curing but excluding the cost of centering, shuttering finishing and reinforcement with: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size	21.64	Cum	10404.52	225174.51
11	Centering and shuttering including strutting, propping etc. and removal of form for:Foundations, footings, bases of columns etc. for mass concrete.	651.47	mpa	262.30	170881.37
12	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	943.50	sqm	573.85	541429.77
13	Suspended floors, roofs, landings, balconies and access platforms.	59.20	sqm	635.60	37630.06
14	Lintel, beams, plinth beams, girders, bressumers and cantilevers.	80.43	sqm	502.85	40446.24
15	Arches domes, vaults upto 6 m span	177.19	sqm	2086,80	369751.74
16	Extra for shuttering in circular work (20% of respective centering and Shuttering items)Foundations, footings, bases of columns etc. for mass concrete.	651.47	sqm	52.46	34176.27
17	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	943.50	sqm	114.77	108285.95
18	Lintel, beams, plinth beams, girders, bressumers and cantilevers.	80.43	sqm	100.57	8089.25
19	Arches, domes, vaults upto 6 m span	177.19	sqm	417.36	73950.35
20	Edges of slabs and breaks in floors and walls	50.98	m	242.30	12351.48
21	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	2970.00	kgs	57.90	171963.00
22	Steel reinforcement for R.C.C. work ready to use "cut and bend" rebars of approved make from factory/workshop to construction site including placing in position and binding all complete upto plinth level.TMT bars	27297.50	Kg	87.18	2379659.48

111	r
u	2

Mary Contract of the Contract					40
3	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete welded	12703.42	Kg	102.14	1297463.39
	12mm Cement plaster finished with a floating coat of neat cement of mix:1 : 3 (1 cement : 3 fine sand)	541.61	sqm	343.75	186178.78
25	1 : 4 (1 cement : 4 fine sand)	1796.90	sqm	325,45	584799.80
	1 : 6 (1 cement : 6 fine sand)	88.70	sqm	241.75	21442.98
27	Finishing walls with water proofing cement paint of required shade on New work (two or more coals applied @ 3.84 kg/10sqm)	1796.90	sqm	91.80	164955.05
28	Painting with synthetic enamel paint of approved brend and manufacture to give an even shade two or more coats on new work	480.00	sqm	121.95	58536.00
29	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-incharge.Made of G.I. wire of dia 4 mm	864.00	sqm	733.50	633744.00
30	Carriage of materials by mechanical transport including loading, unloading, stacking of materials -	236.73	Cum	208.28	48830.69
24	SAND: 5kms Beyond 5 km upto 10 km per km	236.73	Cum	14.92	3530.99
31	Beyond 10 km upto 20 km per km	236.73	Cum	12.14	2874.79
32	Beyond 20 km per additional km (40Kms)	236.73	Cum	9.94	2352.10
33	Carriage of materials by mechanical transport including loading, unloading, stacking of materials -	362.31	Cum	206.28	74735.24
	Aggregate 20mm 5kms	362.31	Cum	14.92	5404.17
35	Beyond 5 km upto 10 km per km	362.31	Cum	12.14	4399.86
36	Beyond 10 km upto 20 km per km	362.31	Cum	9.94	3599.88
38	Beyond 20 km per additional km (40Kms) Carriage of materials by mechanical transport including loading, unloading, stacking of materials -	52.68	Cum	224.20	11810.62
	Aggregate 40mm and above : 5kms	52.68	Cum	16.22	854.17
39	Beyond 5 km upto 10 km per km	52.68	Cum	13.20	695.45
40	Beyond 10 km upto 20 km per km	52.68	Cum	10.76	567.03
41	Beyond 20 km per additional km (40Kms) Carriage of materials by mechanical transport including loading, unloading, stacking of materials -	147.59	M.T	183.36	27061.15
	Steel/ CGI Sheets:5kms	147.59	M.T	13.26	1957.02
43	Beyond 5 km upto 10 km per km	147.59	M.T	10.80	1593.80
44	Beyond 10 km upto 20 km per km	147.59	M.T	8.83	1303.50
46	Beyond 20 km per additional km (40Kms) Carriage of materials by mechanical transport including loading, unloading, stacking of materials - Cement: 5kms	17.75	M.T	183.36	3254.94
47	Beyond 5 km upto 10 km per km	17.75	M.T	13.26	235.39
48	Beyond 10 km upto 10 km per km	17.75	M.T	10.80	191.70
49	Beyond 20 km per additional km (40Kms)	17.75	M.T	8.83	156.79
50	Carriage of materials by mechanical transport including loading, unloading, stacking of materials - Bricks: 5kms	9308.48	1000 No	0.51	4710.09
51	Beyond 5 km upto 10 km per km	9308.48	No -	0.40	3695.47
52	Beyond 10 km upto 20 km per km	9308.48	No	0.32	3006.64
53	Beyond 20 km per additional km (40Kms)	9308.48	No	0.27	2466.75
	Carriage of materials by manual means including	7477134-4-5	TVE T	CANALOS C	40599 10
54	loading, unloading, stacking of materials; (Sand) ist	236.73	Cum	209.90	49688.10

			_
		41	
		×	
1	U	ď.	>
	•	P.,	

	Total alloted cost after Adding 4% to DPR-AA	Service .	CHI HOLD	A ROPERTY	V V
	Restricted amount to cost of DPR/DAP				109.20lacs
	Toati::;				105.00 lacs
68	P/L of stone dust incl. carriage of M.t 20 Km	10.03	Cuiti	1	12597625.13
	roller. Diff. of stone dust incl. carriage of M.t 20 Km	10.03	Cum	679.82	6818.5
67	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening /binding material to fill up interstices of coarse aggregate, watering and compacting to the required density.	125.42	Cum	710.85	89154.8
66	Supply of stone screening 13.2 mm incl lead of 55kms	22.57	Cum	1156.62	2010-03
65	Supplying and stacking at site incl lead of 55kms Grade II 63 - 45mm (Quarry)	144.85	Cum	1273.51	184467.92 26104.91
64	P/ Laying of Nalah stone boulders/nallah mukh/RBM. Incl. carriage by M.T lead 10 kms & incl. rolling with power roller and watering of same.	292.00	Cum	938.47	274033.24
63	Surface Excavation of ground including disp. of exc. earth disposed earth to be levelled and neatly dressed in : All kinds Of Solls	1463.42	SQm	83.45	122121.98
62 k	carriage of materials by manual means including bading, unloading, stacking of materials- Brick ist 50m	9308.48	No	0.39	3639.62
61 10	arriage of materials by manual means including ading, unloading, stacking of materials- Cement ist Om	17.75	M/T	121.57	2158.06
io los	arriage of materials by manual means including ading, unloading, stacking of materials- Steel/CGI neets ist 50m	147.59	M.T	261.10	38534.64
	yond lst 50m 1000Mtrs Avg	52.68	Cum	49.40	2602.50
8 108	rriage of materials by manual means including ding, unloading, stacking of materials- Aggregate mm and Above ist 50m	52.68	Cum	226.92	11953.59 2602.50
	yond 1st 50m 1000Mtrs Avg	362.31	Cum	45.70	16557.79
Bel	ding, unloading, stacking of materials- Aggregate ow 40mm ist 50m	362.31	Cum	209.90	76047.51

d conditions:::
The alloted cost of the work is Rs109.20 lacs (Rupees One Crore Nine lac Twenty thousands only). However the alloted cost should in no case exceed beyond DAP/DPR.
The work shall have to be completed within a period of (70) days from the date of issuance of this allotment order, failing which penalty upto 10% of the total value shall be imposed upon you.
Earnest money deposited by you Vide FDR No 689203 1Dated 17/12/203 For Rs152000.00 and No 689564 dated 27/07/2023 for Rs80.000 and shall be released only after the successful completion of work and after the expiry of defect clause.
The date of start of work shall be reckoned within one week from the date of issuance of this Contract allotment
After testing and commissioning of work the bidder will have to make a trial run of the work for a period of 03 months during which the bidder will have to operate and maintain the executed work to the full satisfaction of the Department, the DLP. In case any defect remains unantended by the firm at the completion of DLP, the department may extend the DLP for such time as deeded fit for getting the defect rectified subject to maximum ceiling of 06 months
֡֡֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜֜

1	he deficts Liability period shall be for a period of 12 Months which shall commence after the successful completion of Trai run he bidder shat be responsible to make good & remedy at his own expense any defect in works which is noticed during the DLP is case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time the bidder shall be responsible for the time and proper setting out of all the works and for the correctness of the positions levels timensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in as beened for getting the defect rectified subject to a maximum ceiling of 6 Months
	The rates are including the Charges for Submission of progress Geo-tagged photographs, vediographic record flatourly the professional person before during & after construction and progress reports in both hard and soft copies Taking Cross-Sections 1, Sections by Auto Level/ETS before and atter execution Preparation of work abstract of executed work, preparation of bills besides the rates quoted/alloted are inclusive of taxes and the tees viz OST/Income tax/Ceas etc shall be deducted at source from running account bills.
9	All the Cement RCC Steel plumbing and other works shal be strictly as per relevant 15 Codes CPHEEO norms/requirements/specifications and normal PWD pracautions
10	You shall be solely responsible for enrying out the mandatory tests required or as decided by Engineer-in-charge for the quality control at your own costs. The cost of conducting all tests shall be done by the contractor and shall be deemed to have been included in the term rates for various items of work and percentage rate tendered Nothing extra shall be payable on this account.
11	You have to furnish the confirmatory survey, strucetual & functional design including geo-technical analysis, soil investigation and quality control tests done at your level duly vetted by DIGC as per terms & conditions of the NIT The vetting charges for the
12	of monitoring and evaluation of the performance of the Contract on mg
13	approved by the competent authority
14	No price escalation will be paid for completion of the work within stipulated time or extended data of completion due to 223y reason whatsoever
15	No extra claim towards any type of tax, freight etc shall be entertained whatsoever.
16	No mobilisation advance shall be paid Retention money/Security deposit shall be 10% of the contract value. The Security Deposit is to be recovered at the rate of 10% of the contract value.
18	In the event of allottee falling, declining, neglecting or delaying the supplies/works or in the event of any damage securing or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of
15	All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the
20	Any failure or commission to carry out the provision of the contract shall not give any claim by the department or bidder one against the other if such failure of commission occurs by the ACT OF GOD which shall include all natural calamities such as fit floods earthquake, hurricane, strikes, roits, embargoes or from any political or other reasons beyond the control of the paries including war, or a state of insurgency
21	The bidder shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, who and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc
22	part of the bidder, or any of his employees during the execution of work. The bidder shall be responsible for the compensation is any, to labour under the existing labour laws of the country
23	In the event of the death or insurity or insolvency or imprisonment of the bidder or where the bidder being a partnership or ferm becomes dissolved or being corporation goes into liquidation, voluntary or otherwise, the contract may, in the option of the Engineerin charge be terminated by notice in writing posted at the site of the works



	-
M	D

J.	The damage caused to the work during execution or prior to actual completion of wondhanding over of the project before defect lability period due to any natural calamity human interference, the same shall be got restored and made good by you at your own cost
15	No damage is caused to existing structures like roads, bridges, buildings or other public utilities as a result of construction of this work. Where ever any damage occures to any public/private infrastructure or public utility, the same shall be rectifed/made good by you at your own cost
26	Adequate precautions be taken for environment and social protection besides, all safety practices in vogue be strictly adhered to during execution of work
27	No objection certificate from the concerned regulatory authority may also be sought whenever required
28	All other terms & conditions will remain same as laid down in the original NIT SBD GFR-2017/ Procurement Manual 2019/Operational guidelines for J3M

Executive Engineer PLPHE JSD Kulgam

Copy to the Superintending Engineer Hydraulic Circle Aantnag for favour of Informati Asstt.Ex.Engineer PHE Sub-Division Kulgam for information AAO Divisional office for information