

**OFFICE OF THE EXECUTIVE ENGINEER SPECIAL PHE, JAL SHAKTI DIVISION, KULGAM**

M/S Mehrajdin Raina (contractor)  
 S/o Nishat Ahmad Raina  
 Hadigam Kulgam  
 Regd No KM/PHED/RCR/2016-17/061/39 of 2022  
 PAN No. CFPN3348C

No. PHE/MWS/ 6448-50  
 Dated: 16-11-22  
 GST No: 01CPNPR3348C1Z1

Allotment order No 97 of 2022-23  
 Dated: 16-11-22

Name of work: Laying/fitting of pipes incl. installation of PHICS as per DAP and other allied works w.s.s. Shurat Khaiba Larosi, Kholao (Retrofitting)  
 Job: This office's 873 No. 24/PHIC of 2022 issued under No. PHE/2022-23 dated 28.05.2022, Division des (Commissioner Kulgam); authorisation No. 375/0/CX of 2022 dated 06.08.2022 issued under No. 8000/106/2022-23 dated 08.08.2022, Superintending Engineer Hydraulic (Civil Assistant)'s order no. 51/Phd/106/2022 dated 11.08.2022 & this office's 101 No. PHE/2022-23 dated 17.08.2022

Accord of Administrative No and date: SE/1/HD/DB/99 of 2021 dated 05-05-2021
Technical sanction No and date: EE/PHE/Kgm/11 of 2022 Dated: 05-09-2022
Advised amount of work Rs 11,99,000
Allotted amount of work Rs 1016167.90
<b>Ten Lakh Sixteen Thousand One Hundred and Sixty Seven</b>

For and on behalf of Lt. Governor of UT of J&K, the contract for the above work is hereby fixed with you on the following rates quoted/accepted by you on the terms and conditions given as under:

Sl. No	Bidder Name	Quoted Percentage	Quoted amount in figures and words
1.00	Mehrajdin Raina (contractor)	-14.10%	0
<b>DESCRIPTION OF ITEMS OF AS PER BOQ</b>			
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides, and rammings of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: all kinds of soil 1 meter from cutting edge	1294.5	Cum 436,000
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	1165.05	Cum 198,700
3	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work, 15 to 20mm nominal bore	1550	m 20,250
4	25 mm and 32 mm dia. G.I. pipes	800	m 30,650
5	40 mm and 50 mm dia. G.I. pipes	2060	m 40,800
6	65 mm and 80 mm dia. G.I. pipes	882	m 73,050
7	100 mm and 150 mm dia. G.I. pipes	1000	m 107,700
8	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete 20 to 40mm nominal bore	35	each 666,250
9	60 to 80 mm nominal bore	10	each 1266,250
10	Carriage of G.I./D.I. pipes below 100mm dia from Stocking yard to the site by mechanical means	24.47	each 4466,721
11	Beyond 5 km upto 10 km per km	24.47	each 66,300
12	Carriage of G.I./D.I. pipes 100mm dia from Stocking yard to the site by mechanical means 50m	1000	Mtr 4,500
13	Beyond 5 km upto 10 km per km	1000	Mtr 16,300
14	Carriage of G.I./D.I. pipes below 100mm dia from dumping site to actual site of work by manual means 50m	24.47	each 153,249
15	Beyond 1st 50m	24.47	each 22,494
16	Carriage of G.I./D.I. pipes 100mm dia from dumping site to actual site of work by manual means 100m	1000	Mtr 4,150
17	Beyond 1st 50m	1000	Mtr 6,070
<b>Total</b>			
Total allotted cost after deduction of -14.10% as per the quoted percentage of the bidder			1016167.90

**Terms and conditions:**  
 1 The allotted cost of the work is Rs 1016167.90 (Rupees ten lac sixteen thousand one hundred sixty seven only)  
 2 The date of start shall be reckoned from the date as mentioned in the L.O.U/allotment.  
 3 The work shall have to be completed within a period of (90) days from the date of issuance of this allotment order, failing which penalty upto 10% of the total value shall be imposed upon you.  
 4 Earnest money deposited by you Vide G.CDRR/PTDR/ 3/098470 dated 18-08-2022 for Rs 3,60,000 & Rs 3,60,000/- which shall be released only after the successful completion of work and after the expiry of defect clause.  
 5 The contractor/firm shall have to attend the Divisional office with enlistment card for drawal of agreement with three days from the date of issuance of this allotment order. However non-drawal of agreement will not prevent the contract from being enforced upon you.  
 6 The allotted work shall be subject to check by the third party monitoring agency engaged by the department.  
 7 The defect liability period shall be for a period of 12 months which shall commence after the successful completion of trial run. The bidder shall be responsible to make good and remedy at his own expenses any defect in works which is noticed during the DLP. In case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time as decided fit for getting the defect rectified subject to maximum ceiling of 06 months.  
 8 The pre- and post Geo-tagged photographic evidence to be taken prior during execution of work and shall have to be produced in the form of submission of work done claim.  
 9 All other conditions shall be applicable as provided in the standard Bidding document.  
 10 The terms and conditions not provided in the SBD, shall be strictly dealt in accordance with the rules/regulations prescribed in 1075-2019 and Manual for procurement of work 2019.

Copy to  
 1. Superintending Engineer Hydraulic Circle Anantnag for favour of inf.  
 2. Asst. Ex. Engineer PHE, Jal-Division Kulgam for information  
 3. AAO Divisional office for information  
 4. Divisional Drawing branch for information

Signature of Executive Engineer  
 PHE, JSD Kulgam