

Pahulgama
JJM
2022

**OFFICE OF THE EXECUTIVE ENGINEER PHE, JAL SHAKTI DIVISION
BIJBEHARA**

Name:- Mehraj-Ud-din Wani (Kaloo)
S/o Gull Mohd Wani
R/O:- Latroo Alshmuqam
Regd. No:- 167/AA/SE/HYD/BUD/2002-03
GST NO. 01AASPW4473F1ZE

No. *PHB/654-56*
Dt. *20-4-2021*

Advt. Cost Ra 76.59 Lacs
Alloted. Cost Ra 76.59 Lacs

Time for completion: ___ days

Head of Account = JJM

Subject:- Retrofitting of WSS. Bradhanji for providing 100 percent FHTC by way of Constt. of 0.08 lac gallons SR and P/F of GI pipes for WSS Bradhanji (Jal Jeevan Mission) and 03 years maintenance incl 01 year DLP


Reference:- Your Tender in response to this office e-NIT No. 42 of 2020-21 issued vide No. 8711-35 dt: 24-03-2021


For & on behalf of Lt. Governor of Union territory of J&K, contract for above noted work is here by fixed with you on the following quoted rates :-

S.No		Qty.	Unit	Alloted Rates	Amount
1.00	Earth work in excavation by manual means in trenches foundations drains pipes cables etc (Not exceeding 1.5m in width) and for shafts wells cesspits and not exceeding 10 sqm on plan depth upto 1.5m incl disposal of excavated earth upto 1m from cutting edge disposed earth to be levelled and neatly dressed in				
1.10	40% ordinary rock 60% all kinds of soil	132.73	Cum	648.74	86107.26
1.20	50% all kinds of soil 50% ordinary rock	2100.00	Cum	701.92	1474032.00
2.00	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material : All kinds of soil :	49.77	Cum	81.65	4063.72
3.00	P/L of stone soling hand packed	3.72	Cum	616.40	2293.01
4.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	3.72	Cum	4419.85	16441.84
5.00	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:0.5:3 (1 cement : 1/2 coarse sand : 3 graded stone aggregate 20 mm nominal size)	7.44	Cum	7091.60	52761.50
6.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	10.17	Cum	8552.85	86982.48
7.00	Reinforced cement concrete work in arches, archribs, domes, vaults shells, folded plate and roofs having slope more than 15° upto floor five level level including curing but excluding the cost of centering, shuttering finishing and reinforcement with: 5.5:1 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.96	Cum	9458.65	18538.95
8.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Hot rolled deformed bars	1761.00	KG	79.25	139559.25
9.00	Centering and shuttering including strutting, propping etc. and removal of form for:				0.00
9.10	Raft	2.65	Sqm	262.30	695.10
9.20	Walls	90.38	Sqm	573.85	51864.56
9.30	Dome	15.65	Sqm	2086.80	32658.42
10.00	12mm Cement plaster finished with a floating coat of neat cement of mix:1 : 3 (1 cement : 3 fine sand)	111.73	Sqm	343.75	38407.19
11.00	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	140.00	KG	57.90	8106.00
12.00	Providing/fixing of GI pipes incl. MS flanges by welding @ 1 pair per pipes with nuts, bolts washers complete job (Light Class)				0.00
12.10	80mm dia GI pipe	3600.00	Mtr	848.00	3052800.00
12.20	65mm dia GI pipe	2000.00	Mtr	733.00	1466000.00
13.00	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work) Light Class				0.00
13.10	65mm dia GI pipe	1000.00	Mtr	628.45	628450.00
13.20	15mm dia GI pipe	600.00	Mtr	144.40	86640.00
14.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	1890.00	Cum	198.70	375543.00

[Signature]

15.00	Carriage of pipes from divisional store to nearest dumping site & incl loading, unloading & stacking by mechanical transport avg 52kms				0.00
15.10	Cement/steel	11.13	MT	556.75	6196.63
15.20	Sand/stone agg	32.00	Cum	490.00	15680.00
15.30	Stone soling	3.72	Cum	736.96	2741.49
16.00	Extra carriage of materials by manual labour from dumping site to actual site of work for avg distance of 200mtrs.				0.00
16.10	Cement/steel	11.13	MT	152.24	1694.43
16.20	Sand/stone	32.00	Cum	301.74	9655.68
16.30	Stone soling	3.72	Cum	354.98	1320.53
Rates checked as per approved C/S				Total:-	7659233.04
				Rs: 76.59 LACS	


Head Draftsman


Executive Engineer
PHE/ Division Bijbehara

Terms & Conditions

- 1 The cost of work should in no case exceed beyond Rs 76.59 Lacs (Rupees Seventy Six Lac Fifty Nine
- 2 The work shall have to be completed within a period of ___ days from the date of issuance of this allotment order failing which penalty upto 10% of the total value of contract shall be imposed upon you.
- 3 You have to attend the Divisional Office along with your enlistment card for drawl of agreement within three days from the date of issuance of this allotment order. However non drawl of agreement will not prevent the contract from being enforced upon you.
- 4 All other terms & conditions will remain same as laid down in the original NIT / PWD form No 25- double. And FC-33

Copy to the :-

- 1 Superintending Engineer Hyd. Circle Anantnag for favour of information
- 2 Assistant Executive Engineer PHE Sub -Division Pahalgam for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with approved proposals, besides the amount of work does not exceed beyond the provision of allotment in any case for which he shall be personally responsible.
- 3 File concerned