

OFFICE OF THE EXECUTIVE ENGINEER PHE, JAL SHAKTI DIVISION

Patel Jm 27/3/21
28-04-2021

Name:- FAROOQ AHMAD DARZI
S/o MOHD. ABDULLAH
R/O:- Bijbehara
Regd. No:- 41-CEE/SE/HYD/ANG/200809
GST NO. 01BGND8050R1Z3

No 14B/660-62
Dt 28-04-2021

Advt. Cost Rs 18.05Lacs
Alloted. Cost Rs 18.01 Lacs

Time for completion: 45 days ✓
Head of Account = JJM ✓

Subject:- Construction of 0.05 lac gallons capacity SR, Sluice Chamber, P/F of pipes and chain link fencing for Providing 100% FHTC of WSS. Lalwan under (Jal Jeevan Mission) and 03 years maintenance incl 01 year DLP

Reference:- Your Tender in response to this office e-NIT No. 40 of 2020-21 issued vide No. 8560-85 dt: 16-03-2021


For & on behalf of Lt. Governor of Union territory of J&K, contract for above noted work is here by fixed with you on the following quoted rates :-

S.No	Items of work	Qty.	Unit	Alloted Rates	Amount
1.00	Earth work in excavation by manual means in trenches foundations drains pipes cables etc (Not exceeding 1.5m in width) and for shafts wells cesspits and not exceeding 10 sqm on plan depth upto 1.5m incld disposal of excavated earth upto 1m from cutting edge disposed earth to be levelled and neatly dressed in 60% ordinary rock and 40% all kinds of soil	480.00	Cum ✓	551.95	264936.00
2.00	P/L of stone soling hand packed	5.00	Cum ✓	616.40	3082.00
3.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	4.13	Cum ✓	4619.85	19079.98
4.00	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	3.55	Cum ✓	7491.6	26595.18
5.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	25.20	Cum ✓	6277.45	158191.74
6.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	8.51	Cum ✓	8552.85	72784.75
7.00	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15 landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.64	Cum ✓	8953.95	14684.48
8.00	Centering and shuttering including strutting, propping etc. and removal of form work for:				0.00
9.00	Foundation	100.00	Sqm ✓	262.36	26236.00
10.00	Walls	108.72	Sqm ✓	573.85	62388.97
11.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Hot rolled deformed bars	1129.00	KG ✓	85.00	95965.00
12.00	P/F of MS lid of required size complete job	2.00	No ✓	Free of Cost	0.00
13.00	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. made of G.I. wire of dia 4 mm	74.00	Sqm ✓	733.50	54279.00
14.00	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade new work (two or more coats) incld priming cot of approved brand and manufacture	74.00	Sqm ✓	97.69	7229.06
15.00	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work) Light Class				0.00
16.00	65mm dia GI pipe	215.00	Mtr ✓	628.45	135116.75
17.00	50mm dia GI pipe	400.00	Mtr ✓	477.50	191000.00
18.00	40mm dia GI pipe	150.00	Mtr ✓	386.05	57907.50
19.00	25mm dia GI pipe	400.00	Mtr ✓	249.00	99600.00
20.00	20mm dia GI pipe	300.00	Mtr ✓	182.65	54795.00
21.00	15mm dia GI pipe	350.00	Mtr ✓	144.40	50540.00

Patel Jm

22.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	372.00	Cum	198.70	73916.40
23.00	Providing/fixing of GI pipes incl. MS flanges by welding @ 1 pair per pipes with washers, nuts, bolts etc complete job Light Class				0.00
24.00	65mm dia GI pipe	250.00	Mtr	733.00	183250.00
25.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	290.00	Kg	92.85	26926.50
26.00	Carrage of materials from their respective sources upto nearest dumping site incl loading, unloading & stacking by mechanical transport				0.00
27.00	Cement/steel avg 42kms	15.66	MT	479.95	7516.02
28.00	Sand/stone agg avg 48kms	58.09	Cum	574.46	33370.38
29.00	Stone soling agg avg 35kms	5.00	Cum	564.07	2820.35
30.00	Extra carrage of materials from dumping site to actual site of work by manual labours avg lead 1200mtrs				0.00
31.00	Cement/steel	15.66	MT	583.14	9131.97
32.00	Sand/stone agg	58.09	Cum	1096.54	63698.01
33.00	Stone soling agg	5.00	Cum	1209.98	6049.90
Rates checked as per approved C/S				Total:-	1801090.94
				Rs: 18.01 LACS	


Head Draftsman


Executive Engineer
PHE, Division Bijehara

Terms & Conditions

- 1 The cost of work should in no case exceed beyond Rs 18.01 Lacs (Rupees Eight Lac One Thousand only)
- 2 The work shall have to be completed within a period of 45 days from the date of issuance of this allotment order falling which penalty upto 10% of the total value of contract shall be imposed upon you.
- 3 You have to attend the Divisional Office along with your enlistment card for drawl of agreement within three days from the date of issuance of this allotment order. However non drawl of agreement will not prevent the contract from being enforced upon you.
- 4 All other terms & conditions will remain same as laid down in the original NIT / PWD form No 25- double. And FC-33

Copy to the :-

- 1 Superintending Engineer Hyd. Circle Anantnag for favour of information
- 2 Assistant Executive Engineer PHE Sub -Division Pahalgam for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with approved proposals, besides the amount of work does not exceed beyond the provision of allotment in any case for which he shall be personally responsible.
- 3 File concerned