

Government of Jammu & Kashmir
Office of the Executive Engineer, PHE (Jal Shakti) Division Chadoora

ALLOTMENT LETTER (JJM)

No: PHEDC/ 7817-22
 Dated: 02-01-2023

M/S: Mohammad Amin Khoja
 S/o: Ab Rahman Khoja
 R/o: Daulatpora Chadoora
 Regd: SE/Hyd/Bud/AYY/107/Civil/2002-03
 GST In: 01A0HPK7133H129
 Pan No: ACHPK7133H

Adv. Cost: Rs.105.77 lac (One Crore Five Lacs Seventy Seven Thousand only)
 Allotted Cost: Rs.9364745.00 (Rupees Ninety Three Lacs Sixty Four
 Thousand Seven Hundred Forty Five only)
 Earnest Money: Rs.211540.00
 Time of completion: 40days.
 Head of account: Jal Jeevan Mission (JJM)

Subject: Allotment for: Laying and fitting of pipes for WSS Nowbugh.

- Reference:
- Your tender in response to this office e-NIT No: 06/PHEDC of 04/2022 (2022-23) issued vide endorsement No: PHEDC/332-42 Dated. 20-04-2022.
 - Chief Engineer, Kmr. Jal Shakti PHE Department Srinagar's No. CE/PHE/MC/DB/13745-83 Dated. 26-07-2022.
 - District Dev. Commissioner, Budgam's Authorization No. 6027-47 Dated 01.08.2022.
 - Superintending Eng., Hyd. Circle Budgam's No. SE/Hyd/Bud/2640-42 Dated 01-08-2022.
 - This office L.O.I No. PHEDC/3321-28 Dated. 04-08-2022.

For and on behalf of the Lt Governor of Jammu & Kashmir UT the contract for above noted work is fixed with you on the following quoted rates, terms and conditions:

| S. | Items of work | Qty. | Unit | Rate | Amount |
|----|---|---------|--------|---------|------------|
| 1 | Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: All kinds of Soil | 3011.29 | Cum | 436.00 | 1312922.41 |
| 2 | Mechanical means | 6579.2 | Cum | 188.75 | 1241824.00 |
| 3 | Metallic Surface | 557.07 | Cum | 646.05 | 359895.07 |
| 4 | Laying in position of pipes: 200/150/100/80mm DI K7 | 4397.05 | Qtl | 245.55 | 1072695.63 |
| 5 | Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket: 200 mm dia pipes | 946.00 | No | 213.00 | 201498.00 |
| 6 | 150mm dia pipes | 3092.0 | No | 144.70 | 447412.40 |
| 7 | 100mm dia pipes | 501.00 | No | 89.70 | 44939.70 |
| 8 | 80mm dia pipes | 251.00 | No | 80.50 | 20205.50 |
| 9 | Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work: 65mm dia G.I pipes | 500.00 | Rm | 73.05 | 36525.00 |
| 10 | 50mm dia G.I pipe | 1000.0 | Rm | 40.80 | 40800.00 |
| 11 | 40mm dia G.I pipes | 1000.0 | Rm | 40.80 | 40800.00 |
| 12 | 25mm dia G.I pipes | 3300.0 | Rm | 30.65 | 101145.00 |
| 13 | 20mm dia G.I pipes | 2000.0 | Rm | 20.25 | 40500.00 |
| 14 | Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete: 15 to 40 mm dia nominal bore | 80.00 | No | 666.25 | 53300.00 |
| 15 | 50 mm to 80 mm dia nominal bore | 50.00 | No | 1268.75 | 63437.50 |
| 16 | Manufacture/Providing and fixing of MS Flanged joints including cutting of pipes, threads, cost of nuts bolts, rubber jams, testing (complete): 150mm dia. | 26.00 | Joints | 2150.00 | 55900.00 |
| 17 | 100mm dia | 75.00 | Joints | 1520.00 | 114000.00 |
| 18 | 80mm dia | 60.00 | Joints | 1100.00 | 66000.00 |

Drawing Branch

Government of Jammu & Kashmir
Office of the Executive Engineer, PHE (Jal Shakti) Division Chadoora

ALLOTMENT LETTER (J/M)

No: PHEDC/ 7017-22
 Dated: 02-01-2023

| | | | | | |
|----|---|---------|-----|---------------|------------------|
| 19 | Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m. | 9109.85 | Cum | 198.70 | 1810127.20 |
| 20 | Providing and fixing of regulatory devices of reputed make including all carriages complete: 150mm dia sluice valve | 16.00 | No | 26720.00 | 427520.00 |
| 21 | 100mm dia sluice valve | 4.00 | No | 17210.00 | 68840.00 |
| 22 | 80mm dia sluice valve | 4.00 | No | 10815.00 | 43260.00 |
| 23 | 200mm dia NRV | 1.00 | No | 45000.00 | 45000.00 |
| 24 | 150mm dia NRV | 1.00 | No | 15000.00 | 15000.00 |
| 25 | 100mm dia NRV | 2.00 | No | 12000.00 | 24000.00 |
| 26 | 80mm dia NRV | 3.00 | No | 9000.00 | 27000.00 |
| 27 | Providing and fixing 50mm dia C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc. if required will be paid separately): | 15.00 | No | 5147.15 | 77207.25 |
| 28 | Fabrication and Providing and fixing of MS Flanged bends, Tee's etc at required spots including earthwork refilling and all carriages: 200/150mm dia | 50.00 | No | 12000.00 | 600000.00 |
| 29 | 100mm dia | 20.00 | No | 9000.00 | 180000.00 |
| 30 | Providing/fixing of pipe specials including all carriages complete: 40mm dia Elbow | 80.00 | No | 250.00 | 20000.00 |
| 31 | 25mm dia Elbow | 80.00 | No | 200.00 | 16000.00 |
| 32 | 20mm dia Elbow | 80.00 | No | 150.00 | 12000.00 |
| 33 | 40mm dia Union | 150.00 | No | 350.00 | 52500.00 |
| 34 | 25mm dia Union | 150.00 | No | 250.00 | 37500.00 |
| 35 | 20mm dia Union | 150.00 | No | 150.00 | 22500.00 |
| 36 | 40x25mm Reducer | 100.00 | No | 140.00 | 14000.00 |
| 37 | 25x20mm Reducer | 100.00 | No | 110.00 | 11000.00 |
| 38 | 40mm dia Nipple | 200.00 | No | 60.00 | 12000.00 |
| 39 | 25mm dia Nipple | 200.00 | No | 50.00 | 10000.00 |
| 40 | 20mm dia Nipple | 200.00 | No | 40.00 | 8000.00 |
| 41 | Providing and laying in position cement concrete of specified grade including curing, the cost of centring and shuttering. All work upto plinth level with including mud mat: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including earth work, soling and all carriages complete job. | 20.00 | Cum | 6682.00 | 133640.00 |
| 42 | Carriage of various materials by Mechanical transport from different source upto the dumping site of work including loading, un-loading and stacking etc avg lead 15 Kms: 200 mm dia D.I pipe | 5200.0 | Mtr | 14.47 | 75244.00 |
| 43 | 150 mm dia D.I pipe | 17000 | Mtr | 8.90 | 151300.00 |
| 44 | 100 mm dia D.I pipe | 3000.0 | Mtr | 5.33 | 15990.00 |
| 45 | 80 mm dia D.I pipe | 1500.0 | M.T | 2.17 | 3255.00 |
| 46 | 65 to 20 mm dia G.I pipe | 19.98 | M.T | 217.09 | 4337.46 |
| 47 | Carriage of pipes various materials from Dumping site of work to actual site of work by manual labour / ponies including handling / rehandling complete job. Avg.lead 800mtrs. | 5200.0 | Mtr | 24.37 | 126724.00 |
| | | | | Total: | 9364745.1 |

(Rate & quantity checked)

Head Draftsman

[Signature]

Executive Engineer
 Jal Shakti PHE Division
 Chadoora

[Signature]

Drawing Branch



Terms and conditions

1. The work shall have to be started by you at site immediately and ensure its successful completion within a period of 150 days from the date of issuance of LOI from this office strictly in accordance with the proposals failing which the shall have to be executed through any other means at your risk and cost, the CDR deposited by you security against this contract shall be forfeited.
2. Date of start of the work shall be reckoned with in 07 days from the date of issue of LOI. However, date of start for laying and fitting of pipes will start within two days of issuance of pipe materials by the department.
3. An agreement shall have to be drawn up by you with the department within a period of 7 days from the date of issuance of allotment failure to execute such a formal deed shall however prevent the contract from being enforced upon you.
4. The allotted works shall be subject to check by third party monitoring agency appointed by the department.
5. Payment shall be released as per actual and measured work done not less than 20% of allotted cost.
6. Performance security equivalent to 03% of the value of the contract is to be deposited by you in shape of CDR/FDR/Bank Guarantee valid for a period of 03 months beyond expiry of warranty period of the contract.
7. The firm shall be bound for satisfactory performance of works for 03 months after the successful commissioning of the work. If during warranty period any malfunctioning/defect arises, you shall have to rectify the same within a period of ten days of receipt of intimation. In case of any failure on your part, then department may get the defects removed/repared any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under relevant clause of contract including black listing.
8. After testing and commissioning of works you shall have to make a trial run of the works for a period of three months during which you have to operate and maintain the executed works to the full satisfaction of the department.
9. Any item of work not included in the allotment but required for the completion of the work, shall be executed by the contractor, as directed by the department. Such extra item shall be paid at J&K SSR 2020 rates with allotted appreciation/depreciation of the contractor. In case such item does not figure in J&K SSR 2020, the same shall be paid as per the current market rate analysis, to be approved by the competent authority.
10. The defect liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
11. The advertised quantities in the tender documents are tentative and subject to increase or decrease depending upon actual requirement at site as per the design and other considerations.
12. Pre & post geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
13. All other terms and conditions shall be applicable as laid down in standard bidding document (SBD) and PWD form No. 25/33.
14. Any rules/terms and conditions if not stipulated in the bidding document, shall be strictly deemed in accordance with the terms and conditions stipulated in General Financial Rules (GFR-2017) and Manual for procurement of works 2019 G.O.I.
15. The agency shall adhere to and comply with orders and instructions of the Engineer in charge and Third Party Inspection and Monitoring Agency and any other verification agency.

Executive Engineer,
Jal Shakti PHE Division
Chadoora

Copy to the:

1. Chief Engineer, Kashmir Jal Shakti PHE Department Srinagar, for favour of information.
2. Superintending Engineer Hydraulic Circle Budgam (Member Secretary DJJM) for favour of information.
3. Asstt. Ex. Engineer Jal Shakti PHE Sub-Division _____ for Information and necessary action. He shall ensure execution of work as per JJM guidelines, monitoring by TPIMA, and observance of all relevant IS codes and Government Orders in vogue.
4. M/S WAPCOS Ltd. Humhama for information.
5. AAO/Head Draftsman of Divisional office for information.