

**Government of Jammu & Kashmir**  
**Office of the Executive Engineer, PHE (Jal Shakti) Division Chadoora**

**ALLOTMENT LETTER (JJM)**

No: PHEDC/5084-90  
Dated: 03-10-2022

M/S: Ghulam Mohi ud din Shagoo  
S/o: Mohammad Ramzan Shagoo  
R/o: Qamarwari Srinagar  
Regd No: SE/Hyd/Sopore/193/2005-06.  
GST Tin: 01BVZPS2746G1Z5  
Pan No: BVZPS2746G

Adv. Cost: Rs. 87.57 lac (Eighty Seven Lacs Fifty Seven Thousand only)  
Allotted Cost: Rs. 8318791.00 (Rupees Eighty Three Lacs Eighteen Thousand Seven Hundred Ninety One only)  
Earnest Money: Rs. 175140.00  
Time of completion: 50 days  
Head of account: Jal Jeevan Mission (JJM)

- Subject:** Allotment for: Laying/Fitting of pipes for WSS Pohroo.
- Reference:**
1. Your tender in response to this office e-NIT No: 06/PHEDC of 04/2022 (2022-23) issued vide endorsement No: PHEDC/332-43 Dated. 20-04-2022.
  2. Chief Engineer, Kmr. Jal Shakti PHE Department Srinagar's No. CE/PHE/MC/DB/13745-83 Dated. 26-07-2022.
  3. District Dev. Commissioner, Budgam's Authorization No. 6027-47 Dated 01.08.2022.
  4. Superintending Eng., Hyd. Circle Budgam's No. SE/Hyd/Bud/2640-42 Dated 01-08-2022.
  5. This office L.O.I No. PHEDC/2921-27 Dated. 01-08-2022.

For and on behalf of the Lt Governor of Jammu & Kashmir UT the contract for above noted work is fixed with you on the following quoted rates, terms and conditions:

S. No.	Items of work	Qty.	Unit	Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: All kinds of Soil	6298.00	Cum	436.00	2745928.00
2	Metalled Surface	1574.50	Cum	646.05	1017205.73
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	7085.30	Cum	198.70	1407849.11
4	200 mm dia sluice valve	3.00	No	35000.00	105000.00
5	150 mm dia sluice valve	10.00	No	30000.00	300000.00
6	100 mm dia sluice valve	20.00	No	20000.00	400000.00
7	150 mm dia Ductile Iron Class K - 7 Pipes	136.50	Qtl	245.55	33517.58
8	100 mm dia Ductile Iron Class K - 7 Pipes	954.18	Qtl	245.55	234298.90
9	200 mm dia Ductile Iron Class K - 7 Pipes	90.27	Qtl	245.55	22165.80
10	80 mm dia Ductile Iron Class K-7 pipes	393.75	Qtl	245.55	96685.31
11	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes incl. testing of joints & including cost of rubber gasket: 150mm dia pipes	101.00	No	144.70	14614.70
12	100 mm dia pipes	1034.00	No	89.70	92749.80
13	Laying/fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work: 65 mm dia G.I pipes	1000.00	Rm	73.05	73050.00
14	50 mm dia G.I pipe	9000.00	Rm	40.80	367200.00
15	40 mm dia G.I pipes	5500.00	Rm	40.80	224400.00
16	25 mm dia G.I pipes	14000.00	Rm	30.65	429100.00
17	20 mm dia.	9000.00	Rm	20.25	182250.00
18	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete				
19	15 to 40 mm dia nominal bore	30.00	No	666.25	19937.50

Drawing Branch

**Government of Jammu & Kashmir**  
**Office of the Executive Engineer, PHE (Jal Shakti) Division Chadoora**

**ALLOTMENT LETTER (JJM)**

No: PHEDC/ 5084-90  
Dated: 03-10-2022

20	50 mm to 80 mm dia nominal bore	15.00 /	No	1268.75	19031.25
21	P/F C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc. if required will be paid separately): 50mm dia	6.00 /	No	5147.15	30882.90
22	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket 80mm dia	584.00 /	Joint	80.50	47012.00
23	Fabrication and Providing and fixing of MS Flanged bends, Tee's etc at required spots including earthwork refilling and all carriages: 100mm dia	25.00 /	No	5000.00	125000.00
24	80mm dia	22.00 /	No	4000.00	88000.00
25	Manufacture/Providing & fixing of MS Flanged joints including cutting of pipes, threads, cost of nuts bolts, rubber jams, testing (complete): 150mm dia.	30.00 /	Joints	2150.00	64500.00
26	100mm dia	30.00 /	Joints	1520.00	45600.00
27	80mm dia	20.00 /	Joints	1100.00	22000.00
28	Providing / fixing of ISI make Gate valve including all carriages upto site of work including cost of tail pieces, nuts bolts, MS flanges complete job (Kirkoskar or Zolto make): 80 mm dia Sluice valve	12.00 /	No	16000.00	192000.00
29	Carriage of various materials by Mechanical transport from different source upto the dumping site of work including loading, un-loading and stacking etc avg lead 10 Kms: 200 mm dia D.I pipe	300.00 /	Mtr	14.47	4341.00
30	150 mm dia D.I pipe	600.00 /	Mtr	8.90	5340.00
31	100 mm dia D.I pipe	6200.00 /	Mtr	5.33	33046.00
32	80 mm dia D.I pipe	3500.00 /	Mtr	2.17	7595.00
33	65 mm dia G.I pipe	4.50 /	M.T	217.09	976.91
34	50 mm dia G.I pipe	37.62 /	M.T	217.09	8166.93
35	40 mm dia G.I pipe	17.88 /	M.T	217.09	3881.57
36	25 mm dia G.I pipe	28.14 /	M.T	217.09	6108.91
37	20 mm dia G.I pipe	12.78 /	M.T	217.09	2774.41
38	200 mm dia MS Flanges	15.00 /	Joints	1900.00	28500.00
39	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket 200mm dia	51.00 /	Joint	213.00	10863.00
40	Providing and fixing of regulatory devices of reputed make including all carriages complete: 200 mm dia N/R Valve	2.00 /	No	45000.00	90000.00
41	150 mm dia N/R Valve	2.00 /	No	15000.00	30000.00
42	100 mm dia N/R Valve	3.00 /	No	12000.00	36000.00
43	80 mm dia N/R Valve	3.00 /	No	9000.00	27000.00
44	65 mm dia N/R Valve	2.00 /	No	7000.00	14000.00
45	65 mm dia sluice valve	4.00 /	No	12000.00	48000.00
				Total:	8756622.30
				Deduct 5% on advertised cost as quoted by the contractor	437831.12
				Net Total:	8318791.18
	<b>(Rupees Eighty Three Lacs Eighteen Thousand Seven Hundred Ninety One only)</b>				

(Rates & quantity checked)


Head Draftsman

Executive Engineer  
Jal Shakti PHE Division  
Chadoora

Drawing Branch

## Terms and conditions

1. Time of completion is essence of the contract.
2. The work shall have to be started by you at site immediately and ensure its successful completion within a period of 150 days from the date of issuance of this allotment from this office strictly in accordance with the approved proposals failing which the shall have to be executed through any other means at your risk and cost, besides, the CDR deposited by you security against this contract shall be forfeited.
3. An agreement shall have to be drawn up by you with the department within a period of 3 days from the date of issuance of allotment failure to execute such a formal deed shall however prevent the contract from being enforced upon you.
4. The allotted works shall be subject to check by third party monitoring agency appointed by the department.
5. Payment shall be released as per actual and measured work done not less than 20% of allotted cost.
6. Performance security equivalent to 03% of the value of the contract is to be deposited by you in shape of CDR/FDR/Bank Guarantee valid for a period of 03 months beyond the expiry of warranty period of the contract.
7. The firm shall be bound for satisfactory performance of works for 03 months after the successful commissioning of the work. If during warranty period any malfunctioning/defect arises, you shall have to rectify the same within a period of ten days of receipt of intimation. In case of any failure on your part, then department may get the defects removed/repared any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
8. After testing and commissioning of works you shall have to make a trial run of the works for a period of three months during which you have to operate and maintain the executed works to the full satisfaction of the department.
9. The defect liability period shall be for a period of 12 months and shall commence after the successful completion of trail run.
10. Pre & post geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
11. Date of start of the work shall be reckoned with in 07 days from the date of issue of the letter. However, date of start for laying and fitting of pipes will start within two days of issuance of pipe materials by the department.
12. All other terms and conditions shall be applicable as laid down in standard bidding document (SBD) and PWD form No. 25/33.
13. Any rules/terms and conditions if not stipulated in the bidding document, shall be strictly deemed in accordance with the relevant rules/guidelines stipulated in General Financial Rule (GFR-2017) and manual for procurement of works 2019 G.O.I.
14. The agency shall adhere to and comply with orders and instructions of the Engineer in charge and Third Party Inspection and Monitoring Agency and any other verification agency.

  
Executive Engineer,  
Jal Shakti PHE Division  
Chadoora

### Copy to the:

1. Mission Director, Mission Directorate JJM Civil Secretariat Jammu/Srinagar for favour of information.
2. Chief Engineer, Kashmir Jal Shakti PHE Department Srinagar for favour of information.
3. District Development Commissioner Budgam (Chairperson DJJM) for favour of information.
4. Superintending Engineer Hydraulic Circle Budgam (Member Secretary DJJM) for favour of information.
5. Asstt. Ex. Engineer Jal Shakti PHE Sub-Division \_\_\_\_\_ for Information and necessary action. He shall ensure execution of works as per JJM guidelines, monitoring by TPIMA, and observance of all relevant IS codes and Government Orders in vogue.
6. Head Draftsman/Asstt. Accounts Officer/Head Assistant of the Divisional office for information.