

**ALLOTMENT LETTER**

No: PHEDC/

9048-52

Dated: 14-02-2023

185	Applying priming coat:				
186	With ready mixed red oxide Zinc Chromate primer of approved brand and manufacture on steel galvanized iron/steel works	300.00	sqm	52.75	15825
187	With ready mixed red oxide Zinc Chromate primer of approved brand and manufacture on steel work (second coat)	300.00	sqm	28.90	8670
188	Providing and applying of swellable type water stop tape, 19mm x 25mm thick in linear meter (expansive nature) for construction joints treatment of RCC structure such as raft slab, retaining walls, water storage tank and at the junctions of raft slab with the retaining walls etc.. After cleaning the surface, one coat of required primer for swellable water stop tape shall be applied throughout the length of the joint @3.78 litre per 240 running meter. Over the primed surface swellable type water stop tape shall be placed. The work shall be carried out all complete as per specification and the direction of the Engineer-In-Charge. The product performance shall carry guarantee for 10 years against any leakage	17.82	RM	547.60	9758
189	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixed with dash fastener of required dia. and size including necessary filling up of gaps at junctions i.e, at top, bottom and sides with required EPDM rubber / neoprene gasket felt etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-Charge (glazing, panelling and dash fasteners to be paid for separately.): Anodized aluminum (Anodized transparent or dyed to required shade according to IS:1868, minimum anodic coating of grade AC 15)	100.00	Kg	459.31	45931
190	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixed with dash fastener of required dia. and size including necessary filling up of gaps at junctions i.e, at top, bottom and sides with required EPDM rubber / neoprene gasket felt etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-Charge (glazing, panelling and dash fasteners to be paid for separately): Powder coated aluminum (minimum thickness of powder coated 50 microns)	50.00	Kg	449.85	22493
				Total:	13555751
				Add 8% above on all items as per negotiation of rates	
				Total:	14640211
(Rupees One Crore Forty Six Lacs Forty Thousand Two Hundred Eleven only)					

NOTE:
The work for construction of Filtration Plant for WSS Pohroo has been advertised at a cost of Rs.136.43 lacs, after receiving the approved design from the Worhty Chief Engineer some minor changes in quantities were made accordingly the basic amount also got changed from Rs.136.43 lacs to Rs.135.56 lacs.

(Rates & quantity checked)

Head Draftsman

Executive Engineer
PHE (Jal Shakti) Division
Chadoora

Terms Conditions

1. The cost of work shall in no case exceed to allot amount.
2. Earnest Money Rs.50000/-pledged to Financial Advisor / Chief Accounts Officer Kmr, Jal Shakti (PHE) Department Srinagar.
3. Time of completion is essence of the contract.
4. The work shall have to be started by you at site immediately and ensure its successful completion within a period of 180 days from the date of issuance of LOI/Allotment from this office strictly in accordance with the approved proposals falling which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be recommended for forfeiting.
5. An agreement shall have to be drawn by you with the department within a period of 07 days from the date of issuance of allotment, failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
6. The allotted work shall be subject to check by the third party monitoring agency appointed by the department.
7. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
8. Performance security equivalent to 3% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order and valid for a period of 3 months beyond the expiry of warranty period of the contract.
9. The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the work. If during warranty period any malfunctioning / defects arise, you shall have to rectify same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
10. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
11. The quantity allotted shall have to be executed on ground strictly as per the estimates that have been framed in the DPR.
12. All other terms and conditions shall be applicable as laid down in standard bid document and PWD from No. 25/33.
13. Any rule / terms and conditions if not stipulated in the bidding documents, shall be strictly dealt in accordance with the relevant rules / guidelines stipulated in General Financial Rules (GFR-2017) and manual for procurement of works 2019 G.O.I.


Executive Engineer,
Jal Shakti PHE Division
Chadoora

Copy to the:

1. Chief Engineer, Kashmir: Jal Shakti PHE Department Srinagar for favour of information.
2. District Development Commissioner Budgam (Chairperson DJJM) for favour of information.
3. Superintending Engineer Hydraulic Circle Budgam (Member Secretary DJJM) for favour of information.
4. Asstt. Ex. Engineer Jal Shakti PHE Sub-Division _____ for Information and necessary action. He shall ensure execution of work as per JJM guidelines, monitoring by TPIMA, and observance of all relevant IS codes and Government Orders in vogue.