

OFFICE OF THE EXECUTIVE ENGINEER R.W.S. DIVISION GANDERBAL/ SRINAGAR

Sh. Mir Aamir Nazir,
S/o; Nazir Ahmad Mir,
Baniabugh Gbl,
Class:- DEE

Regd.No:- 11/DSE/Hyd/Hand/DEE/Civil/Sanitary/2013-14.

Advertised cost :- 2.51 Lacs
Allotted Cost :- Rs.2,00,800/-
Time of Completion :- 07 days
Head of Acct.:- JJM

35/3

Sub:- Fixation of contract for, Providing of drinking water supply facilities to un-covered Anganwari Centres (Shutkadi Sonamarg-A; Butta Kulan-A; Rayil-B; Rayil-C; Gund-B; Haknar-B; Fraw-A; Sumbal-A Bhat Mohalla; Surfraw Bagh-B upper; Surfraw bagh-B lower Syed Patti; Ganiwan Baktori Mohalla; Ganiwan Thekripati; Ganiwan Gured Pati; Ganiwan Kasanapati; Ganiwan Kachpathri; Ganiwan Kachpathri-A lower; Ganiwan Kachpathri-B upper; Ganiwan Daradwooder-a upper; Yachama-A Haripora; Mammer-B Pakhtoonpati and Mammer-B Raina Mohalla, Akhal, Kawcherwan, Gujarpatti Margund, Wani Mohalla Kangan, Kangan Wudder, Poshker, Pahalnar Wangath, Machkani Wangath, Phat Check Wangath, Yachama and Check Preng (under JJM)

Ref:- Your tender in response to this office Short term e-NIT No:- 35/PHED/RWSD/Civil of 2020-21 (S. No.03). Issued under No:- 8556 – 80, dated:- 04.12.2020.

Allotment order No. RWSD/ 97 of 2020-21,
Dated:- 19-12-20

For and on behalf of the Lieutenant Governor of J&K U.T. the above noted work is hereby allotted to you, on your quoted rates, terms & conditions as laid down here under :-

A). RATES

S. No.	PARTICULARS	QTY.	Unit	RATE (Rs.)	AMOUNT (Rs.)
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: 1 meter from cutting edge				
1.1	In all kinds of soils	230.61	Cum	300.00 (Three hundred)	69183.00
1.2	Ordinary rock	12.69	Cum	800.00 (Eight hundred)	10152.00
2	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work.				
2.1	20 mm dia G.I. pipes	2241.00	RM	20.00 (Twenty)	44820.00
3	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete 25 to 40 mm nominal bore	27.00	each	550.00 (Five hundred fifty)	14850.00
4	Installation of tap post at site incld. cost of 20 mm dia elbow, 20-15 mm dia G.I reducer elbow, 15 mm dia nipples = 50 mm, 15 mm bib cock (brass made) including cost of 16 mm dia steel rod, 1.20 m long to be plugged for tying of post including all costs of re-threading of pipe/ cutting of pipe, complete job	21.00	Job	1174.30 (One thousand one hundred seventy four point thirty)	24660.30
5	Filling available excavated earth excld. rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	218.97	Cum	110.00 (One hundred ten)	24086.70
6	Carriage of pipes from divisional store up to dumping site of work, including loading, unloading and stacking etc. complete by Mechanical Transport				
6.1	pipes for an Avg. lead of 35 Kms.	1.98	M.T.	400.00 (Four hundred)	792.00
6.2	pipes for an Avg. lead of 45 Kms.	1.19	M.T.	500.00 (Five hundred)	595.00
7	Carriage of pipes from dumping site to actual site of work, including loading, unloading and stacking etc. complete by manual labour for an Avg. lead of 300 mtr.				

(K.T.O)

H.D.
M.A.

Exep.
M.A.

7.1	pipes for an Avg. lead of 500 mtr.	1.41	M.T.	300.00 (Three hundred)	423.00
7.2	pipes for an Avg. lead of 300 mtr.	1.19	M.T.	200.00 (Two hundred)	238.00
8	Provision for pipe specials	1.00	Job	11000.00 (Eleven thousand)	11000.00
				G. Total :-	2,00,800/-
(Rupees; Two lacs & Eight hundred) only					

Rates & Qty. Checked
As per Comparative Statement

H.D.

T.O.

B). Terms and Conditions:-

1. This letter of allotment and tender of the contractor will constitute a legal contract and the conditions as laid down in the detailed NIT/PWD form No:-25 & 33 (Double leaf) and hold good even before the drawal of agreement between the contractor and the Department.
2. The contractor is directed to attend the Divisional Office along-with his registration card for drawal of an agreement within a period of (07) days from the date of issuance of this letter of allotment and non-drawal of agreement with the Department does not exclude you from contractual obligations.
3. The total amount of the work on your above quoted rates works out to be **Rs.2,00,800/-** (Rupees; Two lacs & Eight hundred) only.
4. The work is to be completed within a period of 07 days to be reckoned after 3 days from the date of issue of this allotment. In case of any delay caused in the execution of work, penalty upto 10% shall be imposed upon the contractor or the department shall be at liberty to terminate the contract in part or in full (as the case may be) and the contract shall be completed through same other available sources at the risk and cost of the defaultiy agency after serving not more than two notices which should be strictly noted.
5. CDR Nos:-0404461 dated:-21.07.2020 for Rs.1800/-; No. 0404494 dtd:-24.11.2020 for Rs.900/- & No.2906853 dtd:-09.12.2020 for Rs.2400/- are retained in the divisional office as security against the said work and will be released after successful testing, commissioning and handing over the complete contract to the department and additional performance deposit in the shape C.D.R bearing No:- 2906858 dated:-14.12.2020 for Rs.12600/- only.
6. 10% of the amount of the bill shall be retained as "Normal Deposit" in all payments and suitable amount as may be deemed fit shall be held back for successful water test / commissioning of work till defective liability period.
7. All other terms and conditions will be the same as laid down in the detailed Master NIT of the year / PWD form No:-25 double agreement form.

Executive Engineer,

R. W.S. Division Ganderbal/ Sgr.

No:- RWS/Allot/20/

Dated:-

9127-31
19-12-2020

Copy to the:-

1. Superintending Engineer Hydraulic Circle Srinagar for favour of information.
2. Asstt. Ex. Engineer R.W.S. Sub-Division Kangan for information and n/action. He is directed to ensure the work is executed strictly within the provision of the estimate. The progress of work should be strictly monitored and incase of slow progress proper time bound notice should be issued to the contractor and incase the contractor fails to accelerate the progress of work, the case should be recommended for termination and action under rules shall be initiated against the defaulting agency accordingly.
3. Head Draftsman Divisional Office for information.
4. A.A.O. Divisional Office for information.