

Muhammud Bhat,
Qasba Lar Gbl.
DEE

Advertised cost :- 4.65 Lacs
Allotted Cost :- Rs.3,72,000/-
Time of completion:- 05 Days
Head of Acct. :- Jal Jeevan Mission (JJM)

22/02

No. SL(R&B)/Gbl/Bandi/DEE/12/Civil/2019-20.

Fixation of contract for. Retro fitting of water supply. Improvements/ extension of distribution branch for providing water supply at Khimber. Dignibal. Warpoha and Shuhama for WSS's Khimber old. Dignibal and Shuham

Ref:-

Your tender in response to this office Short term e-NIT No:- 22/PHED/RWSD/Civil of 2020-21 (S. No.02). Issued under No:-4116 - 40, dated:- 24.07.2020. And this office letter of Intent No. 4505 - 08, dated:- 06.08.2020.

Allotment order No. RWSD/ 72 of 2020-21,

Dated:- 17-09-20

For and on behalf of the Lieutenant Governor of J&K U.T. the above noted work is hereby allotted to you, on your quoted rates, terms & conditions as laid down here under :-

A). RATES

S. No.	PARTICULARS	QTY.	Unit	RATE (Rs.)	AMOUNT (Rs.)
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 1 Osqm on plan, depth upto 1.5mtr. including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth is to be levelled and neatly dressed in:				
1.1	All kinds of Soil	142.55	Cum	300.00 (Three hundred)	42765.00
1.2	Ordinary rock	97.60	Cum	600.00 (Six hundred)	58560.00
2	Laying and fitting of GI pipes complete exclud. cost of pipes and earthwork:				
2.1	40 mm dia G.I. pipes	500.00	RM	30.00 (Thirty)	15000.00
2.2	25 mm dia G.I. pipes	1750.00	RM	23.00 (Twenty three)	40250.00
2.3	20 mm dia G.I. pipes	1230.00	RM	17.00 (Seventeen)	20910.00
3	Filling available excavated earth exclud. rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	216.05	Cum	190.00 (One hundred ninety)	41049.50
4	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete				
4.1	25 to 40 mm nominal bore	15.00	Each	600.00 (Six hundred)	9000.00
4.2	50 to 80 mm nominal bore	1.00	Each	1500.00 (One thousand five hundred)	1500.00
5	Cutting road and making good the same including supply of extra quantities of material i.e. aggregate, moorum screening, red bajri and labour required.				
5.1	Butmuminous portion (Quarry).	3.00	Cum	3000.00 (Three thousand)	9000.00
5.2	Water bound macadam (Quarry).	18.00	Cum	2200.00 (Two thousand two hundred)	39600.00
6	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 50 mmthick with 20mm nominal size stone aggregate. Crushed.	60.00	Sqm	500.00 (Five hundred)	30000.00
7	Providing and fixing of double flanged joints to G.I. pipes including cutting of threads, welding of flanges, cost of fixtures and fastners with all carriage and head load upto actual site of work having an avg. lead of 20 Kms and lift upto 500 mtrs. complete				
7.1	50 mm dia	77.00	Joint	100.00 (One hundred)	7700.00

(K.T.O)

H.D.



7.3	Flanges for stabilizing existing system 80 mm dia	15.00	Job	1500.00	
7.4	Flanges for stabilizing existing system 50 mm dia	15.00	Job	1500.00	
8	Providing / Fixing of 0.60x0.60 mtr. Size M.S. in whole cover (made up of 5mm thick MS plate & 40x40x5mm angle iron) incl. dng locking arrangements, priming coat and all carriages upto site of work complete job.	2000	Job	4000.00	
9	Carriage of materials by Mechanical transport incld. loading, unloading and stacking from Divisional store. Source upto dumping site of work, complete.				
9.1	Cement / pipe for an avg. lead of 20 Kms	8.00	M.T.	500.00	2420.00
9.2	Sand/ Agg. 20 mm for avg. lead of 20 Kms	3.60	Com	400.00	1440.00
10	Carriage of materials by manual labour incld. loading, unloading and stacking from dumping site to actual site of work, complete for an avg. lead of 500 mts.				
10.1	pipes (below 100 mm dia)	2.43	M.T.	300.00	729.00
11	Provision for pipe specials	1.60	Job	21025.50	21025.50
				G. Total :-	3,72,000/-
(Rupees; Three lacs & Seventy two thousand) only					

Rates & Qty. Checked
As per Comparative Statement

H.D.
4/10/20

abeer
T.O.

Executive Engineer,
RWS
Division Ganderbal Sgr.

B). Terms and Conditions:-

1. This letter of allotment and tender of the contractor will constitute a legal contract and the conditions as laid down in the detailed NIT/PWD form No:-25 & 33 (Double leaf) and hold good even before the drawal of agreement between the contractor and the Department.
2. The contractor is directed to attend the Divisional Office along-with his registration card for drawal of an agreement within a period of (07) days from the date of issuance of this letter of allotment and non-drawal of agreement with the Department does not exclude you from contractual obligations.
3. The total amount of the work on your above quoted rates works out to be **Rs.3,72,000/-** (Rupees; Three lacs & Seventy two thousand) only.
4. The work is to be completed within a period of 05 days to be reckoned after 3 days from the date of issue of this allotment. In case of any delay caused in the execution of work, penalty upto 10% shall be imposed upon the contractor or the department shall be at liberty to terminate the contract in part or in full (as the case may be) and the contract shall be completed through some other available sources at the risk and cost of the defaulting agency after serving not more than two notices which should be strictly noted.
5. CDR No:- 2950171 dated:-30.07.2020 for Rs.9300/- is retained in the divisional office as security against the said work and will be released after successful testing, commissioning and handing over the complete contract to the department and additional performance deposit in the shape C.D.R bearing No:-2950176 dated:- 14.08.2020 for Rs.23250/- only.
6. 10% of the amount of the bill shall be retained as "Normal Deposit" in all payments and suitable amount as may be deemed fit shall be held back for successful water test / commissioning of work till defective liability period.
7. All other terms and conditions will be the same as laid down in the detailed Master NIT of the year / PWD form No:-25 double agreement form.

No:- RWS/Allo/20/
Dated:-

6169-73
17-09-20

RWS

Executive Engineer,
RWS
Division Ganderbal Sgr.

Copy to the:-

1. Superintending Engineer Hydraulic Circle Srinagar for favour of information.
2. Assst. Ex. Engineer RWS Sub-Division Srinagar for information and n/action. He is directed to ensure the work is executed strictly within the provision of the estimate. The progress of work should be strictly monitored and incase of slow progress proper time bound notice should be issued to the contractor and incase the contractor fails to accelerate the progress of work, the case should be recommended for termination and action under rules shall be initiated against the defaulting agency accordingly.
3. Head Draftsman Divisional Office for information.
4. A.A.O. Divisional Office for information.