

Government of Jammu and Kashmir  
Office of the Executive Engineer, Water Supply Master Plan Division, Srinagar.

**M/S Lone & Co.,**  
**Prop.: Abdul Rashid Lone**  
**R/o : Shar Pampore Pulwama**  
**GST : 01ACQPL8949K1ZZ**  
**Regd: 114/AYY/CE/CID/PDC/2010-11**  
**PAN No.: ACQPL8949K**

**Allotment Order No.: 11 of 2023**  
**Dated: 05/2023**

**Subject:-** Allotment for Construction of Retaining Wall on Damaged Side Embankment along the existing Service Reservoir of Aparpora Water Supply Scheme Balmaha. (Under JJM).

**Reference :-** Your tender in response to this office e-NIT No.04/WSMP of 04/2023 dated: 19-04-2023 issued under endorsement No.415-21 dated:19-04-2023 (S. No.01).

**Tender Id:-** 2023\_PHE\_210085\_1

**Advertised Cost:-** Rs.37.67 Lacs (Rupees Thirty Seven Lac and Sixty Seven Thousand Only).

**Allotted Cost:-** Rs.3013600/- (Rupees Thirty Lac Thirteen Thousand and Six Hundred Only).

**Time of Completion:-** 60 Days

**Head of Accounts:-** Jal Jeevan Mission.

For and on behalf of the Lt. Governor, UT of Jammu and Kashmir, the above noted work is hereby allotted to you on the following quoted rates, terms and conditions:-

S.No	Item of Work	Unit	Quantity	Rate	Amount
01.	Earth work in bulk excavation by mechanical means (hydraulic excavator) over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m <sup>2</sup> on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.: i. All kinds of soil :	Cum	487.85	111/Cum (Rupees One Hundred and Eleven Only per Cum)	54151.35
02.	Providing and laying hand packed stone soling (Quarry) 75mm nominal size including ramming and dressing including all leads lifts and all carriages complete.	Cum	24.60	500/Cum (Rupees Five Hundred Only per Cum)	12300.00
03.	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: i. 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	Cum	12.25	3500/Cum (Rupees Three Thousand and Five Hundred Only per Cum)	42875.00
04.	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: i. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	Cum	21.60	6200/Cum (Rupees Six Thousand and Two Hundred Only per Cum)	133920.00

05.	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level i. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	52.50	7000/Cum (Rupees Seven Thousand Only per Cum)	367500.00
06.	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. i. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	Cum	77.00	9000/Cum (Rupees Nine Thousand Only per Cum)	693000.00
07.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. i. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg.	19425.00	73/Kg. (Rupees Seventy Three Only per Kg.)	1418025.00
08.	Centering and shuttering including strutting, propping etc. and removal of form for i. Foundations, footings, bases of columns etc. for mass concrete. ii. Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	Sqm	110.00	200/Sqm (Rupees Two Hundred Only per Sqm)	22000.00
		Sqm	315.00	200/Sqm (Rupees Two Hundred Only per Sqm)	63000.00
09.	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	Sqm	439.07	50/Sqm (Rupees Fifty Only per Sqm)	21953.50
10.	Providing / Cutting / Fixing of PVC Pipes 80mm dia for weep holes. Complete Job.	Job	01	2500/Job (Rupees Two Thousand and Five Hundred Only per Job)	2500.00
11.	Fixing of G.I. Chain Link Febric fencing panels with Structural Steel of required width including strengthening with 2mm dia wire or nuts, bolts and washers / welding / fixing in concrete in level including all loading, lifting complete job as per directions of Engineer Incharge. This items includes all types of carriage from Divisional store.	Sqm	199.50	110/Sqm (Rupees One Hundred and Ten Only per Sqm)	21945.00
12.	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete				

	i. On steel work 13.60.2 On concrete work.	Sqm	199.50	90/Sqm (Rupees Ninety Only per Sqm)	17955.00
13.	Distemping with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/liter, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. i. Two coats	Sqm	386.70	50/Sqm (Rupees Fifty Only per Sqm)	19335.00
14.	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. i. Welded	Kg.	1200.00	95/Kg. (Rupees Ninety Five Only per Kg)	114000.00
15.	Providing and fixing of sign boards at Tube Well site & SR Site on 4mm thick MS board (2'-6" Ht with Structural Steel 50x50x6mm fixed above Gate 12'-0" wide) painted after priming coat with name of Schemes complete job.	No.	02	2899.98/No. (Rupees Two Thousand Eight Hundred Ninety Nine and Paise Ninety Eight Only per No.)	5800.00
16.	Carriage of material from various sources upto site of work by mechanical transport. i. Cement and Steel for an avg. lead of 10Kms. ii. Sand for an avg. lead of 15Kms. iii. 20mm Aggregate for an avg. lead of 5Kms. iv. 40mm Aggregate for an avg. lead of 5Kms.	MT Cum Cum Cum	78.41 70.12 128.21 11.03	11/MT (Rupees Eleven Only per MT) 11/Cum (Rupees Eleven Only per Cum) 11/Cum (Rupees Eleven Only per Cum) 26.84Cum (Rupees Twenty Six and Paise Eighty Four Only per Cum)	863.00 771.00 1410.00 296.00
<b>Total</b>					<b>3013600.00</b>
<b>Rupees Thirty Lac Thirteen Thousand and Six Hundred Only.</b>					

**Terms and Conditions:**

- This letter of allotment / acceptance of the contractor will constitute a legal contract and the conditions as laid down in advertised NIT / rate list printed PWD for 25 double agreement form will hold good even before the drawal of agreement between the contractor and department.
- The time of completion of work is 30 days which shall reckoned from the date of dispatch of this allotment.
- The CDR for **Rs.75500/- (Rupees Seventy Five Thousand and Five Hundred Only)** vide No. 3064788 dated : 08-05-2023 has been retained in this office as security deposit for the work.
- The payment shall be made after placement of funds to this division by the competent authority.
- You are directed to attend the office of under signed within 8 days for drawal of necessary agreement with this department.
- Allotment issued on the basis of individual item rates, which will not be treated as any bench mark for rates.
- All other terms and conditions shall remain same as laid down in detailed NIT & PWD form 25 double.

No. 129499  
Dated 16/5/23  
Rates checked as per Comparative Statement

**Executive Engineer,**  
**Water Supply Master Plan Division,**  
**Srinagar**

**Copy to the:-**

- The Chief Engineer, Kashmir PHE Department, Srinagar for favour of information.
- Superintending Engineer, Hyd. Circle, Srinagar / Ganderbal, Head Quarter Srinagar, for information.
- Asstt. Executive Engineer, Distt. Sub Division 2<sup>nd</sup>, for information and necessary action.
- Asstt. Accounts Officer for information.
- Head Draftsman for information.
- File Concerned.