

Jammu & Kashmir

OFFICE OF THE EXECUTIVE ENGINEER PHE DIVISION SOPORE

M/s Gh. Mohi-U-Din Shagoo
 S/o: Haji Mohd Ramzan Shagoo
 R/o: Barthania Qamarwari Srinagar
 Reg. No.: SE/HYD/Sopore/193/hundred Ninety
 2005-2006
 E-mail ID: gmshagoo1@rediffmail.com
 Phone No: 9906471145
 Position of AAA : Accorded
 Position of T.S : Accorded

No:- 1678-84
 Dated:- 12-05-2023
 Advt. Cost: Rs.58.80 lacs
 Allott. Cost: Rs.56.16 lac
 Time of Complt.: 60 days

Subject: - Construction of Sump Cum Pump House at Stage I & II for W.S.Scheme Sangri Muqam under JJM (Tender Id: 2023_PHE_209929_2).

Ref: 1. Your on-line tender received in response to this office Fresh E-NIT No: 08/JJM/JSDS of 04/2023 dated: 17-04-2023 S.No: 02
 2. Superintending Engineer Hyd. Circle Sopore's Authorization issued vide No: SE/Hyd/DB/1218-30 dated: 06/05/2023

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, contract for the work mentioned above is here by fixed with you on the following rates, terms and conditions.

A Rates:

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
1	Earth work in excavation by mannual means over areas (exceeding 30cm and upto 1.5m in depth and width as well as 10 Sqm in Plan) including disposal of excavated earth upto 1m cutting edge, disposed earth to be levelled and neatly dressed in all kinds of soil.	Cum	730.20	436.00	318367.20
2	Earth work in excavation by mechanical means over areas (exceeding 30cm and upto 1.5mtr in depth, 1.5mtr in width as well as 10 sqm on plan) including disposal of excavated earth upto 50m from cutting edge disposal earth to be levelled and neatly dressed . All kinds of soil	Cum	229.90	252.05	57946.30
3	Extra for earthwork in excavation beyond 1.5m	Cum	528.80	81.65	43176.52
4	Providing and laying of dry Stone soling in horizontal on level.	Cum	21.30	816.40	17389.32

Head Draftsman

Technical Officer

Execn.

Sump Cum Pump House at Stage I & II for W.S.Scheme Sangri Muqam under JJM

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone agg. 40 mm nominal size Crushed)	Cum	12.20	4861.84	59314.45
6	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum	13.80	6344.25	87550.65
7	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	97.40	9408.14	916352.84
8	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. All works upto plinth level.	Cum	11.90	7911.25	94143.88
9	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. All works above plinth level.	Cum	30.90	9302.98	287462.08
10	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations	Sqm	68.90	262.30	18072.47
11	Centering and shuttering including strutting, propping etc. and removal of form for: walls (any thickness) including attached pilasters buttresses, plinth and string course fillets, kerbs and steps etc.	Sqm	498.60	573.85	286121.61


Head Draftsman


Technical Officer

Exer

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
12	Centring and shuttering including strutting, propping etc, and removal of form work for Suspended floors, roofs, landings, balconies and access plat forms.	Sqm	119.60	635.60	76017.76
13	Centering and shuttering including strutting, propping etc. and removal of form for: Lintel , beams & cantilevers etc	Sqm	68.10	502.85	34244.09
14	Centering and shuttering including strutting, propping etc. and removal of form for: Spiral Stair, landings	Sqm	19.20	619.80	11900.16
15	Extra for shuttering in circular work for Foundations, footings, bases for columns	Sqm	10.00	52.46	524.60
16	Extra for shuttering in circular work for Walls	Sqm	205.80	114.77	23619.67
17	Extra for shuttering in circular work for lintels, beams & cantilevers	Sqm	59.34	100.57	5967.82
18	Extra for shuttering in circular work for Spiral stair, landing	Sqm	19.20	123.96	2380.03
19	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm)	Sqm	416.90	91.80	38271.42
20	Applying priming coat:With ready mixed pink or grey primer of approved brand and manufacture on-wood work (hard and soft wood)	Sqm	39.40	59.50	2344.30
21	Distempering with oil bond washable distemper of approved brand and manufacture to give an even shade. New worl one or more coats	Sqm	113.20	149.05	16872.46
22	Providing hoisting and fixing trusses/purlins /rafters/posts/ post-plates or like components including cost of screws etc. complete First class Budloo/Fir wood	Cum	4.00	138685.40	554741.60
23	Providing corrugated G.S sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.50mm thick with zinc coating not less than 275gm/m ²	Sqm	106.50	830.25	88421.63
24	Reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete (T.M.T bars)	Kg	24050.90	87.17	2096516.95
25	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	Kg	1534.70	57.90	88859.13
26	Brick work in FPS bricksof class designation 75 in foundation and plinth in cement mortar 1:4 mix	Cum	29.90	6501.20	194385.88
27	Extra for brick work with common burnt clay bricks/cement concrete bricks in superstructure above plinth level upto floor five level	Cum	14.80	1323.65	19590.02


 Head Draftsman


 Technical Officer


 Exen

Sump Cum Pump House at Stage I & II for W.S.Scheme Sangri Muqam under JJM

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
28	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge, Using First class kail wood 35mm Thick.	Sqm	5.80	3093.80	17944.04
29	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length (hold fast lugs or with dash fasteners shall be paid for separately) 2nd Class Kail Wood	Cum	1.30	92065.35	119684.96
30	Providing and fixing panelling or panelling and glazing in panelled or paneled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40mm thick, for Door	Sqm	2.20	2501.75	5503.85
31	Providing and fixing panelling or panelling and glazing in panelled or paneled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40mm thick, for Glass panes 4mm thick for exterior window shutters	Sqm	8.80	1768.05	15558.84
32	c)Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia wire and 1.4 mm wide aperture with matching wood beading	Sqm	3.10	1454.80	4509.88
33	Extra For Plastering on circular work one coat.	Sqm	254.70	34.35	8748.95
34	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel work	Sqm	9.50	52.75	501.13
35	Painting with synthetic enamel paint of approved brand and manufacture on steel galvanised iron/ steel work	Sqm	48.90	121.95	5963.36
36	Supplying and fixing rolling shutters of approved make, made of required size M.S laths interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete including the cost of providing and fixing necessary 27.50cm long wire springs manufacture from high tensile steel wire of adequate strength confirming to IS 4454 part 1 and M.S top cover of required thickness for rolling shutters. 80x1.25mm M.S laths with 1.25mm thick top cover	Sqm	7.10	3238.20	22991.22

Head Draftsman

Technical Officer

Exe


Sump Cum Pump House at Stage I & II for W.S. Scheme Sangri Muqam under JJM

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
37	Providing and fixing ball bearing for rolling shutters	No	11.00	483.10	5314.10
38	Providing and fixing aluminium handles ISI marked anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade with necessary screws etc complete 125 mm	No	5.00	66.30	331.50
39	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m	Cum	704.70	198.70	140023.89
40	Carriage of material by mechanical transport from source to actual site of work for: Cement & Steel Avg lead 5 Km	M.T	157.10	183.35	28804.29
41	Carriage of material by mechanical transport from source to actual site of work for: Sand for average lead of 20 Km	Cum	79.15	402.29	31841.25
42	Carriage of material by mechanical transport from source to actual site of work for: 40mm aggregate for average lead of 20 Km	Cum	10.85	437.29	4744.60
43	Carriage of material by mechanical transport from source to actual site of work for: Stone Soling for 12 Km	Cum	21.30	358.98	7646.27
44	Carriage of material by mechanical transport from source to actual site of work for: Bricks for average 80 Km	No	7030.00	2.79	19613.70
	Total				5880281.00
	Below 4.50% on all items				264612.00
	Allotted Cost				5615668.00

Rates and quantities checked:


 Head Draughtsman



 Technical Officer


 Executive Engineer
 Jal Shakti PHE Division
 Sopore

Sump Cum Pump House at Stage I & II for W.S.Scheme Sangri Muqam under JJM

B Terms and conditions:

1. Total amount of the work should in no case exceed beyond Rs.5615668.00 (Rs.Fifty six lacs Fifteen Thousand Six Hundred and sixty eight only) which includes all taxes, levies etc.
2. The work shall have to be completed by you within a period of 60 days failing which the panality under rules shall be imposed upon you.
3. Performance security @ **3%** of allotted cost i.e Rs.168470.00 in shape of CDR/BG/FDR shall have be deposited by you in this office within seven days from the date of issue of this allotment from this office failing which action shall be initiated as per SBD of the NIT.
4. An agreement shall have to be drawn by you with the department within a period of 07 days from the date of issuance of allotment, failure to executed such a formal deed shall not however prevent the contract from being enforced upon you. However payment on account of this work shall not be considered in absence of agreement.
5. The earnest money amounting to Rs.118000/= deposited by you in this office as a bid security against the contract vide CDR/FDR/TDR No:794332 dated : 26-04-2023 shall be considered for release once the performance security @ **3%** of allotted amount is deposited by you.
6. The allotted work shall have to be monitored by Third Party Monitoring Agency (WAPCOAS) appointed by the department.
7. All other terms and conditions shall remain same as laid down in E-NIT/ Standard bidding document/PWD from No 25 and GFR-2017.


Assistant Accounts
Officer


Technical officer


Executive Engineer
Jal Shakti PHE Division
Sopore

Copy to the:

- i) Chief Engineer Kashmir Jal Shakti PHE Department Srinagar for favour of information.
- ii) District Development Commissioner Baramulla (Chairperson DJJM) for favour of information.
- iii) Superintending Engineer Hydraulic Circle Baramulla/Bandipora (Member Secretary JJM) for favour of information.
- iv) Assistant Executive Engineer PHE Sub Division Wattlab for information and necessary action.
- v) M/S WAPCOAS Ltd Corporate office 76-C intuitional area sector 18 Gurgon for information
- vi) Head Draftsman for information.
- vii) File Concerned.