

F23-1
Jammu & Kashmir

OFFICE OF THE EXECUTIVE ENGINEER PHE DIVISION SOPORE

M/s Hilal Ahmad Dar

S/o: Ab. Ahad Dar

R/o: Sopore Baramulla

Reg. No: 973/AYY/Civil/Sanitary/CE/KCC/PDC/2009-10

GST No: 01AJXPD9302N3ZW

E-mail ID : hilalahmad08@gmail.com

No: 9064-71
Dated: 30-11-2023

Time of Compl.: 150 days

Subject: - Construction/Testing/Commissioning of over head Tank's (OHT) along with allied works in different divisions/ Districts of Kashmir Province under Jal Javeen Mission.

Ref:

1. Chief Engineer Kashmir Jal Shakti PHE Department Srinagar's letter No: CE/PHE/DB/15444-45 dated: 05-08-2023.
2. Superintending Hyd. Circle Sopore's authorization issued order No: SE/Hyd./DB/5391 dated: 10-08-2023
3. Your on-line tender received in response to E-NIT No: 16/JJM/JSDS of 08/2023 dated: 11-08-2023.
4. This office letter of Intent No: JS/PHE/DB/Spr./6107-12 dated: 08-09-2023

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, contract for the work namely "Construction/ Testing/ Commissioning of 0.50 lac gallons capacity RCC OHT Shell type with Staging Height of 20 Mts including construction Sluice Chamber at Bohripora for W.S.Scheme Bohripora Sheeraz Colony under JJM" is hereby allotted to you in accordance with the terms and conditions as laid down in the bid document read with any amendment if any for an amount of **Rs.89.03 lacs (Rs.Eighty nine lacs and three thousand only)** as per the following item rates along with your quoted overall tender appreciation of 7.99%

A Rates:

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
1.	Earth work in bulk excavation by mechanical means (hydraulic excavator) over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m ² on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil & sluice chamber 3.6x3.6x1m	Cum	654.11	188.75	123463.00
2.	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material : All kinds of soil	Cum	292.09	81.65	23849.00
3.	Pumping out water caused by springs, tidal or river seepage, broken water mains or drains and the like.	KL	844.03	155.55	131289.00
4.	Providing and laying 75 mm size hand packed stone soling (Quarry) including ramming and dressing including all leads lifts and all carriages complete	Cum	77.63	1320.00	102472.00


Head Draftsman


Technical Officer


Extn

Page No: 2nd
Construction of 0.50 lac gallons capacity at Bohripura

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
5.	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	Cum	19.28	4861.84	93765.00
6.	Close timbering in trenches including strutting, shoring and packing cavities (wherever required) complete. Measurements to be taken of the face area timbered). Depth exceeding 1.5 m but not exceeding 3 m	Sqm	29.88	247.75	7403.00
7.	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	159.51	7800.76	1244338.00
8.	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	93.58	9408.14	880413.00
9.	Providing and laying in position ready mixed M-25 grade concrete for reinforced cement concrete work, using flyash and cement content as per approved design mix, manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work including pumping of R.M.C. from transit mixer to site of laying, excluding the cost of centering, shuttering finishing and reinforcement including cost of admixtures in recommended proportions as per IS : 9103 to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer- in - charge.	Cum	49.20	9302.98	457706.00
10.	Extra for providing richer mixes at all floor levels. Note:- Excess/ less cement over the specified cement content used is payable/ recoverable separately. 5.35.1 Providing M-30 grade concrete instead of M-25 grade BMC/RMC. (Note:- Cement content considered in M-30 is @ 340 kg/cum)	Cum	41.81	111.87	4677.00


Head Draftsman


Technical Officer

Exen

Page No: 3rd
Construction of 0.50 lac gallons capacity at Bohripura

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
11.	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	Sqm	42.88	262.30	11247.00
12.	Centering and shuttering including strutting, propping etc. and removal of form for: Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc	Sqm	988.32	573.85	567146.00
13.	Centering and shuttering including strutting, propping etc. and removal of form for: Lintel, beams, plinth beams, girders, bressumers and cantilevers.	Sqm	79.67	502.85	40063.00
14.	Centering and shuttering including strutting, propping etc. and removal of form for: Stairs (excluding landings) except spiral stair cases	Sqm	1.79	807.50	1447.00
15.	Centering and shuttering including strutting, propping etc. and removal of form for: Arches, domes, vaults upto 6 m span	Sqm	93.57	2086.80	195266.00
16.	Centering and shuttering including strutting, propping etc. and removal of form for: Columns, pillars, piers, abutments, posts and struts.	Sqm	10.11	680.15	6874.00
17.	Centering and shuttering including strutting, propping etc. and removal of form for: spiral stair cases (including landings)	Sqm	29.19	619.80	18092.00
18.	Extra for shuttering in circular work (20% of respective centering and Shuttering items).				
19.	Foundations, footings, bases of columns etc. for mass concrete	Sqm	41.00	52.46	2151.00
20.	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc	Sqm	988.317	114.77	113429.00
21.	Lintel, beams, plinth beams, girders, bressumers and cantilevers.	Sqm	79.672	100.57	8013.00
22.	Extra for arches, domes, vaults exceeding 6 m span	Sqm	72.848	1008.45	73464.00
23.	Reinforcement for RCC work including straightening, cutting, bending, binding and placing in position complete TMT	Kgs	22934.34	87.18	1999302.00
24.	Extra for R.C.C./B.M.C./R.M.C. work above floor V level for each four floors or part thereof.	Cum	66.09	309.05	20425.00
25.	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	Kg	442.62	57.90	25628.00


Head Draftsman


Technical Officer


Exen

Page No: 4th
Construction of 0.50 lac gallons capacity at Bohripura

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
26.	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size	Cum	7.00	9849.35	68933.00
27.	Reinforced cement concrete work in arches, arch ribs, domes, vaults shells, folded plate and roofs having slope more than 15° upto floor five level including curing but excluding the cost of centring, shuttering finishing and reinforcement with: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size	Cum	10.59	10404.52	110184.00
28.	Extra for additional height in centering, shuttering where ever required with adequate bracing, propping etc. including cost of de-shuttering and de-centering at all levels, over a height of 3.5 m, for every additional height of 1 meter or part thereof (Plan area to be Measured). Suspended floors, roofs, landings, beams and balconies (plan area to be measured)	Sqm	934.41	267.60	250048.00
29.	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. Layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering lead upto 50m and lift upto 1.5m.	Cum	259.64	198.70	51590.00
30.	Structural steel work welded in built up sections, trusses and framed work incld. cutting, hoisting, fixing in position & applying steel primer all complete.	Kg.	1077.00	146.63	157921.00
31.	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer. M.S tube	Kg	123.37	172.90	21331.00
32.	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer. For Stair	Kg	0.63	500.00	315.00
33.	Providing and fixing 1mm thick M.S. steel door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. (i) Using M.S. angles 40x40x6mm for diagonal braces.	Sqm	1.00	4352.95	4353.00

Head Draftsman

Technical Officer

Exen

Page No: 5th
Construction of 0.50 lac gallons capacity at Bohripura

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
34.	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer	Sqm	1.00	4189.60	4190.00
35.	Providing and fixing ventilator of size 450mmx450mm made out of angle iron 40mmx40mm with wire mesh of 25mmx25mm size including welding charges and including all carriages upto site of work	No	5.00	1500.00	7500.00
36.	Providing and fixing G.I pipes (B medium) complete with G.I fittings excluding trenching and refilling etc (external work) for rising main and delivery main of OHT. 100mm dia nominal bore	Mtr	100.00	1234.95	123495.00
37.	Providing and fixing G.I pipes (B medium) complete with G.I fittings excluding trenching and refilling etc (external work) for rising main and delivery main of OHT. 150mm dia nominal bore	Mtr	200.00	2167.65	433550.00
38.	Providing, fixing of sluice valves flanged type of ISI mark. The job includes cost of nuts, bolts, washers incld. all sorts of carriages upto site of work complete job including cost of sluice valves 80mm	No	3.00	14058.00	42174.00
39.	Providing, fixing of sluice valves flanged type of ISI mark. The job includes cost of nuts, bolts, washers incld. all sorts of carriages upto site of work complete job including cost of sluice valves 100mm dia sluice valve	No	4.00	17210.00	68840.00
40.	Providing, fixing of sluice valves flanged type of ISI mark. The job includes cost of nuts, bolts, washers incld. all sorts of carriages upto site of work complete job including cost of sluice valves 125mm dia sluice valve	No	2.00	21000.00	42000.00
41.	Providing, fixing of sluice valves flanged type of ISI mark. The job includes cost of nuts, bolts, washers incld. all sorts of carriages upto site of work complete job including cost of sluice valves 150mm dia sluice valve	No	2.00	26720.00	53440.00
42.	Providing and fixing of M.S fittings viz bends of suitable degree, tees, collars etc to be fabricated from 6mm nominal size M.S plate as per the requirement of site including cost of welding. The work should be leak proof and should be painted with anti corrosive red oxide primer. Complete job. Mani fold, Bend, tee etc, flanged joint. 100mm	Kg	571.00	147.82	84405.00

Head Draftsman

Technical Officer

Exen

Page No: 6th
Construction of 0.50 lac gallons capacity at Bohripura

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
43.	Providing and fixing of MS flanged joints (8mm to 12mm thick) to double flanged GI/DI pipes including cutting of pipes, welding charges, cutting of flanges, rubber gasket, bolts, nuts including testing of joint and sorts of carriages. Complete Job. 100 mm dia. pipe	Joint	20.00	1520.00	30400.00
44.	Providing and fixing of MS flanged joints (8mm to 12mm thick) to double flanged GI/DI pipes including cutting of pipes, welding charges, cutting of flanges, rubber gasket, bolts, nuts including testing of joint and sorts of carriages. Complete Job. 150 mm dia. pipe	Joint	20.00	2150.00	43000.00
45.	Supply, installation, testing and commissioning of Advanced Maintenance Free environment friendly Earthing system consisting of 1 no. of 3mtr length, 17.2 mm dia UL certified earth electrode made of high tensile low carbon steel circular rods, molecularly bonded copper on outer surface (minimum copper bonding thickness-250 microns) with GI terminals to connect incoming strips, (Environment friendly backfill compound duly certified as per ANSI/NSF standard 60/Toxic content certificate as safe for use near potable ground water resources strictly as per specification enclosed. Make- HREE ELECTRODES/ OBO BETTERMANN / ERICO(2 Nos UPS and 4 Nos Main L.T Panel/2 Nos Fire Fighting Panel)	No	1.00	15800.00	15800.00
46.	Providing and Fixing 25 mm x 5 mm Copper Strip in 40 mm dia. G.I Pipe FRL Earth Electrode including connection with Brass nut ,bolt, spring, washer, excavation and refilling etc. as required.	RM	60.00	1224.00	73440.00
47.	Supply, installation, testing and commissioning of lightening conductor made of 25 mm dia 300 mm long copper tube having single prong at top with base plate.	Each	1.00	1500.00	1500.00
48.	12mm cement plaster of mix 1 : 3 (1 cement : 3 fine sand)	Sqm	399.70	343.75	137397.00
49.	Finishing walls with water proofing cement paint of approved brand and manufacture and of required shade to give an even shade (two or more coats)	Sqm	485.00	91.80	44523.00
50.	Carriage of materials by mechanical transport including loading, unloading, stacking of materials. Cement & Steel for avg. lead 08 kms	M.T	149.576	223.13	33375.00
51.	Carriage of materials by mechanical transport including loading, unloading, stacking of materials. Stone aggregate 40mm for avg. lead 25 kms	Cum	17.16	531.72	9124.00
52.	Carriage of materials by mechanical transport including loading, unloading, stacking of materials. Stone aggregate 20mm for avg. lead 25 kms	Cum	262.30	451.97	118552.00

[Signature]
Head/Draftsman

[Signature]
Technical Officer

[Signature]
EXM


Page No: 7th
Construction of 0.50 lac gallons capacity at Bohripura

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
53.	Carriage of materials by mechanical transport including loading, unloading, stacking of materials. Sand for avg. lead 22 kms	Cum	144.76	422.16	61112.00
	Total				8244414.00
	7.99% above on all items				658728.67
	Grand Total				8903143.00
	Say				89.03 lacs

Rates and quantities checked:


Head Draughtsman


Technical Officer



Executive Engineer
Jal Shakti PHE Division
Sopore

B Terms and conditions:

01. Total value of the work is **Rs.8903143.00 lacs** (Rs.Eighty nine lacs three thousand one hundred and forty three only) worked out on the basis of above quoted rates which includes all taxes, levies etc and as per the drawing provided vide Chief Engineer Kashmir Jal Shakti PHE Department Srinagar's No: **15215-21** dated: **06-08-2022**
02. The date of start of the subject work shall be reckoned from the date of issuance of this allotment order, in case of failure to start the work within three days of issuance of this allotment order action as warranted shall be initiated
03. An agreement shall have to be drawn by you with the department within a period of 07 days from the date of issuance of allotment, failure to execute such a formal deed shall not however prevent the contract from being enforced upon you. However payment shall not be made unless the agreement is drawn.
04. Performance security equivalent to 5% of the value of the contract **Rs.445157.00** valid in accordance with bid conditions, shall have to be furnished by you in shape of CDR/BG/FDR within a week from the date of issuance of this allotment order or at the time of signing of agreement which ever is earlier.
05. All other terms and conditions and technical specifications shall the remain same as laid down in Standard bidding document of the subject E-NIT read with corrigendum minutes of Pre-bid meeting, PWD from No 25 and GFR-17.


Assistant Accounts Officer


Technical officer


Executive Engineer
Jal Shakti PHE Division
Sopore

Copy to the:

01. Mission Director Jal Javeen Mission Civil Secretariat Srinagar for favour of information.
02. Chief Engineer Kashmir Jal Shakti PHE Department Srinagar for favour of Information.
03. District Development Commissioner Baramulla (Chair person DJJM) for favour of information.
04. Direction Planning Jal Shakti Civil Secretariat Srinagar for favour of information.
05. Superintending Engineer Hydraulic Circle Baramulla/Bandipora (Member Secretary JJM) for favour of information.
06. Assistant Executive Engineer PHE Sub Division Wallab for information and necessary action.
07. M/S WAPCOAS Ltd Corporate office 76-C Intuitional area sector 18 Gurgon for information.
08. File Concerned.