

OFFICE OF THE SUPERINTENDING ENGINEER,

JAL SHAKTI DEPARTMENT HYDRAULIC CIRCLE DISTRICT BLA/BPR H.Q SOPORE

Member Secretary District Jal Jeevan Mission Baramulla/Bandipora

Email: sehhydbla@gmail.com

M/S:- Mohd. Shaban Dar

S/o:- Ab. Rashid Dar

R/o:- Dogripora Pulwama

GST No:- 01AKTPD9000E2ZN

Regd No:- 39-AAY/SE/HYD/ANG/2004-2005

Advertised Amount: ₹195.86 lac

Allotted Amount:- ₹1,66,48,173.00

Major Head:-4215-JJM

Time of completion: 180days

ORDER No: 28/SE/HYD/SPR/JJM of 2022-23**Dated: -17-8-2023**

Subject: Fixation of Contract for:

Laying fitting of pipes, 0.75 lac gallons SR, Chowkidar quarter, chain link fencing and sluice chamber for WSS Kanispora under JJM (Tender ID:2023_PHE_220326_1).

Reference:

1. Executive Engineer Jal Shakti (PHE) Division Baramulla's e-NIT No 25 of 07/2023 issued under endorsement No. PHE/BLA/CC/3465-75 Dated 07-07-2023.
2. Revised District Action Plan of District Baramulla approved by DJJM vide no: DDCB/3929 dated: 30-07-2022.
3. Minutes of Meeting held with District Development Commissioner Baramulla (Chairperson DDJM) on 23/5/2022 minutes issued vide letter No DDCB/Meeting/2022/1214-44 Dated: 24/5/2022 and No DDCB/2022/ 1248-70 Dated: 26/5/2022 thereafter vide letter No. DDCB/ 2022/1725-28 Dated 04/06/2022.
4. Administrative Approval Accorded vide Govt Order No: 277-JK(JSD) of 2022 dated: 29-12-2022 issued under endorsement No: JSD-PS/08/2022-PLG-JSD (7019739) dated: 29-12-2022.
5. Technical Sanction issued by Chief Engineer Jal Shakti (PHE) Department Kashmir's Order No:- CE/PHE/DB/805 of 01/2023 Dated: 19-01-2023.
6. Minutes of Meeting of District Contract Committee circulated vide No: SE/Hyd/SPR/5146-58 dated: 05-08-2023.
7. Amendment in operational guidelines for the implementation of Jal Jeevan Mission issued by NJJM, DDW&S ministry of Jal Shakti GOI vide F. No W-11016/10/2022-JJM-IV-DDWS Dated:- 21-06-2022.
8. Modus operandi communicated by Chief Engineer PHE Kashmir Vide circular No CE/PHE/MC/DB/13745-83 Dated: - 26-07-2022.

Dear Sir,

For and on behalf of Lieutenant Governor of Union Territory of Jammu and Kashmir, the contract for above subject work is hereby fixed on the rates quoted by you on Percentage rate basis as per the **Annexure "A"** of this allotment order with standard terms and conditions as laid down in the **Annexure "B"** of this allotment order. The total cost of work shall be **₹1,66,48,173.00 (One Crore Sixty-Six Lac Forty-Eight Thousand One Hundred and Seventy-Three Only)**.

No: SE/HYD/JJM/ 5704-18

Dated:- 17/8/2023

Superintending Engineer
Hydraulic Circle Baramulla/Bandipora
H.Q Sopore.

Copy to the:-

1. Chief Engineer Kmr. Jal Shakti (PHE) Department Srinagar for favour information.
2. District Development Commissioner Baramulla (Chairperson DJJM) for favour of information.
3. Additional District Development Commissioner Baramulla (Member DJJM) for information.
4. Assistant Commissioner Development Baramulla (Member DJJM) for information.
5. Divisional Forest officer Baramulla (Member DJJM) for information.
6. Chief Planning Officer Baramulla (Member DJJM) for information.
7. Chief Medical Officer Baramulla (Member DJJM) for information.
8. Chief Educational Officer Baramulla (Member DJJM) for information.
9. District Social Welfare Officer Baramulla/District Tribal Welfare Officer Baramulla (Member DJJM) for information.
10. District Information officer Baramulla (Member DJJM) for information.
11. Executive Engineer Jal Shakti (PHE) Division Baramulla (Member DJJM) for information and necessary action.
12. Executive Engineer Jal Shakti PHE Mech. Division North Sopore (Member DJJM) for information.
13. Executive Engineer Ground Water Division Srinagar (Member DJJM) for information.
14. WAPCOS Limited Baramulla, for information and necessary action.
15. File Concerned.

No: 6108
Dt: 25-08-2023
ABE(B)
for n/a

(A)

laying fitting of pipes, 0.75 lac gallons SR, chowkidar quarter, chain link fencing and sluice chamber for WSS Kanispora under JJM (Tender ID:2023_PHE_220326_1)

Annexure "A" with Order No. SE/HYD/JJM of 2023-24 Dated :- 17-8-2023

S. No	Item Description	Units	Quantity	Alloted Rate	Amount
	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: All Kinds of soil.	Cum	9762.75	₹ 370.60	₹ 36,18,075.15
1.1	Ordinary Rock	Cum	2434.13	₹ 822.67	₹ 20,02,491.81
2	Earth work in bulk excavation by mechanical means (hydraulic excavator) over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil.	Cum	596.29	₹ 160.44	₹ 95,667.28
3	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil.	Cum	102.10	₹ 458.45	₹ 46,807.49
4	Providing and laying hand packed stone soling 50 mm nominal size including filling, spreading, dressing, ramming, all leads fits and all carriages complete.	cum	32.85	₹ 1,122.00	₹ 36,857.70
5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	cum	18.25	₹ 4,132.56	₹ 75,419.22
6	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum	2.64	₹ 5,931.87	₹ 15,660.15
7	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	cum	55.82	₹ 6,630.65	₹ 3,70,122.66
8	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	cum	24.84	₹ 7,996.91	₹ 1,98,643.36
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	cum	9.11	₹ 8,371.94	₹ 76,268.40
10	Boulder filling in rooms including handpacking and laying etc. complete	Cum	15.68	₹ 552.50	₹ 8,663.20
11	Reinforced cement concrete work in arches, archribs, domes, vaults shells, folded plate and roofs having slope more than 15° upto floor five level level including curing but excluding the cost of centering, shuttering finishing and reinforcement with: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	cum	8.72	₹ 8,843.84	₹ 77,118.27

laying fitting of pipes, 0.75 lac gallons SR, chowkidar quarter, chain link fencing and sluice chamber for WSS Kanispora under JJM (Tender ID:2023_PHE_220326_1)

Annexure "A" with Order No. SE/HYD/JJM of 2023-24 Dated :- 17-8-2023

S. No.	Item Description	Units	Quantity	Alloted Rate	Amount
12	Providing and incorporating G.I Sheet strip 150mm wide and 2.5mm thick during concreting.	Mtr	85.29	₹ 255.00	₹ 21,748.95
13	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum	18.89	₹ 5,495.42	₹ 1,03,808.40
14	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	7961.10	₹ 74.10	₹ 5,89,907.56
15	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns	sqm	194.81	₹ 222.96	₹ 43,433.86
15.1	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	sqm	295.19	₹ 487.77	₹ 1,43,985.56
15.2	Lintel beams, plinth beams, girders, bressumers and cantilevers.	sqm	33.12	₹ 427.42	₹ 14,156.23
15.3	Suspended floors, roofs, landings, balconies and access platforms.	sqm	53.47	₹ 540.26	₹ 28,887.70
15.4	Columns, pillars, piers, abutments, posts and struts.	sqm	7.36	₹ 578.13	₹ 4,255.02
15.5	Arches, domes, vaults upto 6 m span	sqm	70.96	₹ 1,773.78	₹ 1,25,867.43
16	Extra for shuttering in circular work: Foundations, footings, bases of columns etc.	sqm	18.85	₹ 44.59	₹ 840.54
16.1	Walls	sqm	271.63	₹ 97.55	₹ 26,498.73
16.2	Suspended Floors	sqm	6.78	₹ 108.05	₹ 732.59
16.3	Lintel beams etc.,	sqm	33.12	₹ 85.48	₹ 2,831.25
16.4	Extra for arches, domes, vaults exceeding 6 m span.	sqm	70.96	₹ 857.18	₹ 60,825.67
17	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	Cum	27.00	₹ 4,622.08	₹ 1,24,796.13
18	Brick work with common burnt clay (non-modular) bricks of class designation 7.5 in foundation and plinth including curing in Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	21.16	₹ 5,256.19	₹ 1,11,220.93
19	Extra for brick work with common burnt clay bricks/cement concrete bricks in superstructure above plinth level upto floor five level	Cum	15.13	₹ 1,125.10	₹ 17,022.80
20	Providing ridges or hips of width 60cm overall width plain G.S. sheets fixed with polymer coated J. or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete. 0.5 mm thick with zinc coating not less than 275 gram/m ²	Mtr	7.40	₹ 532.70	₹ 3,941.94
21	Providing fixing fabricating of MS plate form made of 5mm thick MS plate in 50x50x6mm angle iron frame incl. all sorts of brackings etc., and supporting channel section as directed by Engineer Incharge, all work as complete job.	Job	1.00	₹ 6,800.00	₹ 6,800.00
22	Providing and fixing of MS ladder of required height made of 50x50x6mm angle section with 40x40x5mm thick treads etc all work as complete job.	Job	1.00	₹ 6,800.00	₹ 6,800.00
23	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	kg	473.00	₹ 49.22	₹ 23,278.70
24	Random Rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 Cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) upto plinth level and curing complete with: Cement mortar 1:6 (1 Cement : 6 coarse sand)	Cum	2.45	₹ 3,740.43	₹ 9,164.04

aving fitting of pipes, 0.75 lac gallons SR, chowkidar quarter, chain link fencing and sluice chamber for WSS Kanispora under JJM (Tender ID:2023_PHE_220326_1)

Annexure "A" with Order No. SE/HYD/JJM of 2023-24 Dated :- 12.8-2023

S. No	Item Description	Units	Quantity	Alloted Rate	Amount
25	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length (hold fast lugs or with dash fasteners shall be paid for separately): KD/ Silver wood	cum	0.57	₹ 46,750.00	₹ 26,647.50
26	12mm Cement plaster of mix: 1 : 6 (1 cement : 6 fine sand)	sqm	60.00	₹ 205.49	₹ 12,329.25
27	12mm Cement plaster finished with a floating coat of neat cement of mix: 1 : 3 (1 cement : 3 fine sand)	sqm	147.74	₹ 292.19	₹ 43,167.78
28	Providing & Fixing of MS door of size(1 x 2.5m)with 3mm Ms sheet thk 40x40x6mm size angle iron frame incl. all accessories, locking arrangements, applying of approved steel primer and all carriages upto the site of work complete job.	No	1.00	₹ 6,800.00	₹ 6,800.00
29	Providing corrugated G. S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface)excluding the cost of purins, rafters and trusses and including cutting to size and shape wherever required. 0.50 mm thick with zinc coating not less than 275 gram/m2	sqm	112.62	₹ 705.71	₹ 79,477.34
30	Providing & fixing of plain Eaves boarding of 2nd CGI sheet 40mm thick & 300mm wide	Mtr	34.30	₹ 595.00	₹ 20,408.50
31	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4mm thick float glass panes including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. KD/ Silver wood	sqm	10.34	₹ 2,125.00	₹ 21,972.50
32	Providing and fixing wire gauze shutters using galvanized M.S. wire gauze of average width for aperture 1.4 mm in both directions with wire of dia. 0.63 mm for doors, windows and clerestory windows with ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws as per direction of Engineer-in-charge : KD/ Silver wood	sqm	10.34	₹ 1,700.00	₹ 17,578.00
33	P/F of pannalled or pannalled doors, windows & celestory windows (area of opening for paneling insert excluding portion inside groves or rebates to be measured) paneling for paneled or paneled and glazed shutters 25 to 40mm thick. KD/ Silver wood	sqm	5.85	₹ 2,125.00	₹ 12,431.25
34	Providing hoisting and fixing trusses/purlins /rafters/ posts/ post plates or like components including cost of screws etc. complete. Popular wood	Cum	2.67	₹ 29,750.00	₹ 79,432.50
35	Providing & fixing White vitreous china water closet squatting pan(Indian type) along with "S" or "P" trap including dismantling of old WC seat and "S" or "P" trap at site complete with all operations including all necessary materials, labour and disposal of dismantled material i/c malba, all complete as per the direction of Engineer-in charge. Orissa pattern W.C Pan of size 580x440 mm	No	1.00	₹ 3,136.71	₹ 3,136.71
36	Providing and fixing Salem Stainless Steel A ISI 304 (18/8) kitchen sink as per I.S. 13983 with C.I. brackets and stainless steel plug 40 mm including painting of fittings and brackets, cutting and making good the walls wherever required: Kitchen sink with drain board 510x1040mm bowl depth 250mm	No	1.00	₹ 6,170.79	₹ 6,170.79

laying fitting of pipes, 0.75 lac gallons SR, chowkidar quarter, chain link fencing and sluice chamber for WSS Kanispora under JJM (Tender ID:2023_PHE_220326_1)

Annexure "A" with Order No: SE/HYD/JJM of 2023-24 Dated :- 17.8-2023

S. No	Item Description	Units	Quantity	Alloted Rate	Amount
37	Providing & fixing PVC soil waste and vent pipe 100mm	Mtr	30.00	₹ 212.50	₹ 6,375.00
37.1	75mm	Mtr	20.00	₹ 170.00	₹ 3,400.00
38	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fitting arrangement of approved quality and colour. 450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm, weighing not less than 170 gms.	No	1.00	₹ 682.30	₹ 682.30
39	Providing & fixing GI pipes complete with GI fittings and clamps including cutting and making good the walls etc. (Internal works). 15mm dia nominal bore. (light weight)	Mtr	20.00	₹ 237.07	₹ 4,741.30
39.1	20mm dia nominal bore. (light weight)	Mtr	10.00	₹ 285.77	₹ 2,857.70
40	Providing & fixing GI pipes complete with GI fittings including trenching and refilling etc. (External works). 15mm dia nominal bore. (light weight)	Mtr	35.00	₹ 113.69	₹ 3,979.06
41	Providing & fixing on Terrace (at all floor levels) polyethelene water storage tank ISI 12701 marked indicating the BIS license no. with cover and suitable locking arrangement and making necessary holes for inlet, outlet and over flow pipes but without fittings and the base support for tank (Syntex, Electroplast, Star, Lotus or equivalent having valid ISI license	Litre	500.00	₹ 5.70	₹ 2,847.50
42	Providing & fixing CP brass Bib cock of approved quality confirming to IS-8931. 15mm dia nominal bore.	No	6.00	₹ 271.02	₹ 1,626.14
43	Providing & fixing CP brass angle valve for basin mixer and gyser points of approved make confirming to IS-8931. 15mm dia nominal bore.	No	4.00	₹ 455.69	₹ 1,822.74
44	Providing & fixing of 50 litre capacity gyser of approved quality (venus make or equivalent) incld all sorts of fitting viz angle valves mixer connecting pipe etc	No	1.00	₹ 16,150.00	₹ 16,150.00
45	Providing & fixing Lighting points in 1.5 sqmm multistrand PVC wire to be laid in conduits including providing & fixing of 5-A switches complete.	No	20.00	₹ 1,020.00	₹ 20,400.00
46	Providing & fixing heating points in 2.5 sqmm multistrand PVC copper wire to be laid in conduits including providing & fixing of 16-A switches complete.	No	3.00	₹ 1,275.00	₹ 3,825.00
47	Providing & fixing of 1200mm sweep ceiling fans complete with accessories including dimmer of ISI mark complete.	No	2.00	₹ 2,975.00	₹ 5,950.00
48	Providing & fixing of Exhaust fan in 1.5 sqmm stand wire to be laid in conduits complete.	No	2.00	₹ 2,125.00	₹ 4,250.00
49	Providing & fixing of 16-A MCB of Indocap complete.	No	5.00	₹ 510.00	₹ 2,550.00
50	Providing & fixing MCB distribution box 10 way main double door system.	No	1.00	₹ 4,675.00	₹ 4,675.00
51	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50 mm thick with 20mm nominal size stone aggregate.	sqm	86.96	₹ 472.18	₹ 41,060.34
52	Providing and fixing aluminium handles for door stopper ISI marked anodised (anodi coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade with necessary screws etc complete 125mm size	Nos	3.00	₹ 46.11	₹ 138.34
52.1	100mm size	Nos	10.00	₹ 41.18	₹ 411.83
53	Providing & fixing aluminium hanging floor door stopper ISI marked anodized (Anodic coating not less than grade AC 10 as per IS-1868) transparent or dyed to required colour or shade with nuts and screws etc. complete	No	3.00	₹ 29.92	₹ 89.76

Superintending Engineer

Head Draftsman

laying fitting of pipes, 0.75 lac gallons SR, chowkidar quarter, chain link fencing and sluice chamber for WSS Kanispora under JJM (Tender ID:2023_PHE_220326_1)

Annexure "A" with Order No: 28/SE/HYD/JJM of 2023-24 Dated :- 17-8-2023

S.No	Item Description	Units	Quantity	Alloted Rate	Amount
54	15mm thick cement plaster finished without floating coat of neat cement of mix 1:6 mix (1 cement : 6 fine Sand).	sqm	150.33	₹ 139.10	₹ 20,911.28
55	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturers specifications including appropriate priming coat preparation of surfaces, etc complete.	sqm	287.58	₹ 160.48	₹ 46,150.84
56	Providing 40x5mm flat iron hold fasts 40cm long incl. fixing to frame with 10mm dia bolts, nuts, and wooden plugs and embeddings in cement concrete block 30x10x15cm (1:3:6) mix 20mm nominal size.	No	32.00	₹ 96.73	₹ 3,095.36
57	Providing & fixing aluminium sliding door bolt ISI marked annodized (Anodic coating not less than grade AC 10 as per IS-1868) transparent or dyed to required colour or shade with nuts and screws etc. complete.	No	3.00	₹ 106.34	₹ 319.01
58	Providing & fixing aluminium tower bolt ISI marked annodized (Anodic coating not less than grade AC 10 as per IS-1868) transparent or dyed to required colour or shade with nuts and screws etc. complete.	No	6.00	₹ 54.32	₹ 325.89
58.1	150x10mm	No	20.00	₹ 40.46	₹ 809.20
59	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	100.00	₹ 77.37	₹ 7,737.13
60	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	sqm	137.25	₹ 623.48	₹ 85,571.94
61	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Riveted and bolted.	kg	1752.38	₹ 89.90	₹ 1,57,539.40
62	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with fine sand including finishing the top smooth and curing complete.	sqm	24.75	₹ 422.15	₹ 10,448.27
63	Providing & fixing MS grill of required pattern in frames of windows etc. with Ms flat, square or round bars etc. including priming coat with approved steel primer. All complete.	Kg	300.00	₹ 102.00	₹ 30,600.00
64	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturers) of 1st quality conforming to IS: 15622 of approved make, laid on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete. In all colours, shades, except White, Ivory, Fume Red Brown	sqm	23.47	₹ 948.43	₹ 22,259.65
65	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc complete. On steel work.	sqm	137.25	₹ 160.48	₹ 22,025.88
66	Laying and fitting of G.I. pipes (all classes) complete including cost of pipe specials and excluding cost of Pipes and Earth work. 15 mm dia nominal bore	Mtr	3000.00	₹ 17.21	₹ 51,637.50
66.1	20 mm dia nominal bore	Mtr	5000.00	₹ 17.21	₹ 86,062.50
66.2	25 mm dia nominal bore	Mtr	6000.00	₹ 26.05	₹ 1,56,315.00
66.3	40 mm dia nominal bore	Mtr	8000.00	₹ 34.68	₹ 2,77,440.00
66.4	50 mm dia nominal bore	Mtr	6050.00	₹ 34.68	₹ 2,09,814.00

Laying fitting of pipes, 0.75 lac gallons SR, chowkidar quarter, chain link fencing and sluice chamber for WSS Kanispora under JJM (Tender ID:2023_PHE_220326_1)

Annexure "A" with Order No: SE/HYD/JJM of 2023-24 Dated :- 17-8-2023

S. No	Item Description	Units	Quantity	Alloted Rate	Amount
66.3	65 mm dia. nominal bore	Mtr	7900.00	₹ 62.09	₹ 4,90,530.75
66.4	80 mm dia. nominal bore	Mtr	1400.00	₹ 62.09	₹ 86,929.50
67	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe)	Qtl	1051.30	₹ 208.72	₹ 2,19,424.71
68	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket.	No	731.00	₹ 123.00	₹ 89,909.35
68.1	150 mm dia pipes	No	4.00	₹ 181.05	₹ 724.20
69	200 mm dia pipes	No	4.00	₹ 181.05	₹ 724.20
69	Filling available excavated earth (excluding rock) in trenches, pits, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	cum	11334.90	₹ 168.90	₹ 19,14,407.94
70	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete	No	10.00	₹ 566.31	₹ 5,663.13
70.1	25 to 40 mm nominal bore	No	15.00	₹ 1,078.44	₹ 16,176.56
70.1	50 to 80 mm nominal bore	No	15.00	₹ 1,078.44	₹ 16,176.56
71	Manufacturing providing fixing of MS Bends/ Tees including carriage of welding machine upto site of work incl. cost of nuts, bolts, rubber washers etc., complete job.	Kg	350.00	₹ 178.50	₹ 62,475.00
72	Providing and fixing D.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately). Confirming to IS:14846 read with latest amendments.	No	6.00	₹ 9,192.75	₹ 55,156.50
72.1	80mm dia.	No	6.00	₹ 11,189.40	₹ 67,136.40
72.2	100 mm dia.	No	11.00	₹ 17,206.55	₹ 1,89,272.05
72.3	150 mm dia.	No	3.00	₹ 26,943.30	₹ 80,829.90
73	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end)	No	4.00	₹ 462.27	₹ 1,849.09
73.1	25 mm nominal bore	No	4.00	₹ 599.00	₹ 2,395.98
73.2	40 mm nominal bore	No	4.00	₹ 801.34	₹ 3,205.35
74	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc. if required will be paid separately).	No	4.00	₹ 1,275.00	₹ 5,100.00
74.1	20 mm dia.	No	4.00	₹ 1,700.00	₹ 6,800.00
75	Providing and fixing of MS surface boxes (0.75x0.75) of 6mm thick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete.	Job	6.00	₹ 5,950.00	₹ 35,700.00
76	Providing and fixing of MS flanged joints (12mm thick) to GI/DI pipes including cutting of pipes, welding charges, cutting of flanges, rubber gasket, bolts, nuts including testing of joint and all sorts of carriages. Complete Job.	joint	2413.00	₹ 1,292.00	₹ 31,17,596.00
77	Providing fixing D.I Tail Piece male/ female to D.I pipes one side socketed and one side flanged incl. all carriages complete.	No	5.00	₹ 3,400.00	₹ 17,000.00
77.1	100mm dia D.I	No	6.00	₹ 3,825.00	₹ 22,950.00
78	Carriage of material from source to site of work by Mechanical Transport including loading unloading and stacking etc. Pipes (below 100mm dia) for an average lead of 08 Km	M ton	127.29	₹ 189.66	₹ 24,142.43
78.1	50mm dia D.I pipe for an average lead of 08 Km	Mtr	4024.00	₹ 7.76	₹ 31,231.67
78.2	Cement /Steel for an average lead of 10 Km	M ton	66.51	₹ 212.21	₹ 14,113.81
78.3	Sand/ aggregate 20mm nominal size for an average lead of 25 Km	cum	218.36	₹ 384.18	₹ 83,888.90

laying fitting of pipes, 0.75 lac gallons SR, chowkidar quarter, chain link fencing and sluice chamber for WSS Kanispora under JJM (Tender ID:2023_PHE_220326_1)

Annexure "A" with Order No. SE/HYD/JJM of 2023-24 Dated :- 17.8.2023

S. No	Item Description	Units	Quantity	Alloted Rate	Amount
78.4	Stone aggregate 40mm nominal size for an average lead of 25 Km	cum	16.42	₹ 417.60	₹ 6,856.96
78.5	Soling Stone for an average lead of 25 Km	cum	2.45	₹ 451.97	₹ 1,107.32
78.6	Bricks for an average lead of 75 Km	No	17722.00	₹ 1.40	₹ 24,779.79
79	Cartage of material from dumping/ road side to site of work by Manual Means including loading unloading and stacking etc. for an average lead of 500 Mtrs Pipes (below 100mm dia)	M.ton	127.29	₹ 302.34	₹ 38,484.95
79.1	150mm dia D.I Pipes	Mtr	4000.00	₹ 11.47	₹ 45,866.00
79.2	Cement	M.ton	58.55	₹ 302.34	₹ 17,702.05
79.3	Steel	M.ton	7.96	₹ 302.34	₹ 2,406.63
79.4	Sand/ aggregate 20mm nominal size	cum	218.36	₹ 528.03	₹ 1,15,299.75
79.5	Stone aggregate 40mm nominal size	cum	16.42	₹ 570.82	₹ 9,372.88
79.6	Soling Stone	cum	2.45	₹ 1,078.18	₹ 2,641.55
Total					₹ 1,66,48,173

(One Crore Sixty Six lac Forty Eight Thousand One Hundred and Seventy Three Only)

Head Draftsman

Superintending Engineer
Hydraulic Circle Baramulla/Bandipora
H.Q Sopore

Head Draftsman

Superintending Engineer