

Office of the Executive Engineer (USD) P.H.E Division Anantnaga

E-Mail ID: pshd@anantnaga@gmail.com

M/S Manzoor Ahmad Sheikh
S/o: Ab Rehman Sheikh
R/O: Lajpora
Reg. No: BEE/PHE/SE/A&P/1998-99
PAN No. BCDPS2242E
GST No. 01BCDPS2242E123
Cell No. 9596211090

No. PHE/ANP/ 3022-27
Dated: 29-11-24

Subject:- Supplying, Fabrication, Erection and Commissioning of Structural Steel Scaffolding, RCC foundation, roofing etc. excluding SMC-GFRP Tanks for mounting of Over-head SMC-GFRP panel tank depending on safe bearing capacity, staging height and storage capacity of 0.70 Lac Gallons for Retreating of WSS Lehighs & under Jal Bevan Mission (JBM)

Reference:- (1) Your tender in response to E-NT No. 33 of 2023-24 issued under endorsement No. CE/PHE/JBM/32755-79 dated:- 30.12.2023, Tender Id No. 2023_PHE_241687_1-23.
(2) Minutes of Meeting of Tender Evaluation Committee Convened on 18-10-2024.
(3) Administrative Approval accorded by Chief Engineer Kmr., Jai Shakti (PHE) Deptt. Srinagar's order No. CE/PHE/DB/JBM/377 of 12/2023 dated:- 30.12.2023.
(4) Letter of Acceptance vide Chief Engineer Kmr., Jai Shakti (PHE) Deptt. Srinagar's No. CE/PHE/JBM/36175-86 dt:- 25.11.2024
(5) Technical Sanction Order No. CE/PHE/DB/986 of 11/2024 dated:- 15.11.2024
(6) JBM Meeting held on 13.07.2024 vide No. SE/Hyd/Spr/DB/965-67 dated:- 12.07.2024
(7) This office letter of Intent No. Awm/PHE/307-18 dated:- 16.07.2024
For on behalf of Lieutenant Governor of Union Territory of Jammu & Kashmir, contract for above mentioned work is hereby fixed with you at the following quoted rates, terms conditions.

Advertised Cost- Rs 108.86 lacs

✓ Alloted Cost- Rs 79.618 lacs

(Rupees Seventy Nine Lacs Sixty One Thousand & Eight Hundred) only


S.No.	Particulars of items	Unit	Qty	Estt. Rate	Amount	
					in Figures	in Words
1.00	Earth work in bulk excavation by mechanical means (hydraulic excavator) over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil :	✓ Cum	✓ 459.00	✓ 187.30	85972.57	Rupees EightyFive Thousand Nine Hundred SeventyTwo Paise FiftySeven Only
2.00	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil :	✓ Cum	✓ 196.72	✓ 592.90	116635.29	Rupees One Lakh Sixteen Thousand Six Hundred ThirtyFive Paise TwentyNine Only
3.00	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material : All kinds of soil :	✓ Cum	✓ 258.86	✓ 89.75	23232.69	Rupees TwentyThree Thousand Two Hundred ThirtyTwo Paise SixtyNine Only
4.00	Providing and laying hand packed stone soling (Quarry) 75mm nominal size including ramming and dressing including all leads lifts and all carriages complete.	✓ Cum	✓ 9.89	✓ 1320.00	13054.80	Rupees Thirteen Thousand FiftyFour Paise Eighty Only
5.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	✓ Cum	✓ 4.95	✓ 5202.90	25754.36	Rupees TwentyFive Thousand Seven Hundred FiftyFour Paise ThirtySix Only


[Signature]
Sd/-

[Signature]
Sd/-

Supplying, Fabrication, Erection and Commissioning of Structural Steel Staging, RCC foundation, roofing etc. excluding
 SMC-GFRP Tanks for mounting of Over-head SMC-GFRP panel tank depending on safe bearing capacity, staging height and
 storage capacity of 0.70 Lac Gallons for Retrofitting of WSS Lethpore # under Jal Jeevan Mission (JJM)

6.00	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement: 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	✓ 20.52	✓ 7798.40	159817.97	Rupees one lac fifty nine thousand eight hundred seventeen and paise ninety seven
7.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering, shuttering, finishing and reinforcement. 1:1½:3 (1 cement: 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	✓ 5.29	✓ 9395.70	49703.25	Rupees FortyNine Thousand Seven Hundred Three Paise TwentyFive Only
8.00	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1½:3 (1 cement: 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	✓ 9.03	✓ 9821.85	88691.31	Rupees EightyEight Thousand Six Hundred NinetyOne Paise ThirtyOne Only
9.00	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	sqm	✓ 41.48	✓ 286.35	11877.798	Rupees Eleven Thousand Eight Hundred SeventySeven Paise Eighty Only
9.01	Lintel, beams, plinth beams, girders, bressumers and cantilevers.	sqm	✓ 80.28	✓ 577.55	46365.714	Rupees FortySix Thousand Three Hundred SixtyFive Paise SeventyOne Only
9.02	Columns, pillars, piers, abutments, posts and struts.	sqm	✓ 46.98	✓ 742.55	34884.999	Rupees ThirtyFour Thousand Eight Hundred EightyFive Only
10.00	Steel reinforcement for R.C.C. work ready to use "cut and bend" rebars of approved make from factory/workshop to construction site including placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	✓ 3835.00	✓ 123.20	472472.000	Rupees Four Lakh SeventyTwo Thousand Four Hundred SeventyTwo Only
11.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	Cum	✓ 465.95	✓ 218.40	101763.480	Rupees One Lakh One Thousand Seven Hundred SixtyThree Paise FortyEight Only
12.00	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete Riveted and bolted	Kg	✓ 50043.00	✓ 142.90	7151144.70	Rupees SeventyOne Lakh FiftyOne Thousand One Hundred FortyFour Paise Seventy Only
12.01	welded	kg	✓ 6900.00	✓ 138.20	953580.00	Rupees Nine Lakh FiftyThree Thousand Five Hundred Eighty Only


 Sd/-
 24/04/24



1001	Handwritten text describing a process or event.	✓	✓	✓
1002	Handwritten text describing a process or event.	✓	✓	✓
1003	Handwritten text describing a process or event.	✓	✓	✓
1004	Handwritten text describing a process or event.	✓	✓	✓
1005	Handwritten text describing a process or event.	✓	✓	✓
1006	Handwritten text describing a process or event.	✓	✓	✓
1007	Handwritten text describing a process or event.	✓	✓	✓
1008	Handwritten text describing a process or event.	✓	✓	✓
1009	Handwritten text describing a process or event.	✓	✓	✓
1010	Handwritten text describing a process or event.	✓	✓	✓
1011	Handwritten text describing a process or event.	✓	✓	✓
1012	Handwritten text describing a process or event.	✓	✓	✓
1013	Handwritten text describing a process or event.	✓	✓	✓
1014	Handwritten text describing a process or event.	✓	✓	✓
1015	Handwritten text describing a process or event.	✓	✓	✓
1016	Handwritten text describing a process or event.	✓	✓	✓
1017	Handwritten text describing a process or event.	✓	✓	✓
1018	Handwritten text describing a process or event.	✓	✓	✓
1019	Handwritten text describing a process or event.	✓	✓	✓
1020	Handwritten text describing a process or event.	✓	✓	✓

Supplying, Fabrication, Erection and Commissioning of Structural Steel Staging, RCC foundation, roofing etc. excluding SMC-GFRP Tanks for mounting of Over-head SMC-GFRP panel tank depending on safe bearing capacity, staging height and storage capacity of 0.70 Lac Gallons for Retrofitting of WSS Lethpora A under Jal Jeevan Mission (JJM)

22.01	Beyond 5 km upto 10 km per km	Cum	✓ 49.97	✓ 15.86	3912.65	Rupees Three Thousand Nine Hundred Twelve Paise SixtyFive Only
22.02	Beyond 10 km upto 20 km per km	Cum	✓ 49.97	✓ 13.08	6541.07	Rupees Six Thousand Five Hundred FortyOne Paise Seven Only
23.00	Carriage of materials by mechanical transport including loading, unloading, stacking of materials - Aggregate 40mm and above :5 Km	Cum	✓ 4.45	✓ 218.18	970.95	Rupees Nine Hundred Seventy Paise NinetyFive Only
23.01	Beyond 5 km upto 10 km per km	Cum	✓ 4.45	✓ 17.03	378.92	Rupees Three Hundred SeventyEight Paise NinetyTwo Only
23.02	Beyond 10 km upto 20 km per km	Cum	✓ 4.45	✓ 14.23	633.24	Rupees Six Hundred ThirtyThree Paise TwentyFour Only
24.00	Carriage of materials by mechanical transport including loading, unloading, stacking of materials - Cement / Steel/ CGI Sheets: 5 Km	MT	✓ 18.975	✓ 178.43	3385.71	Rupees Three Thousand Three Hundred EightyFive Paise SeventyOne Only
24.01	Beyond 5 km upto 10 km per km	MT	✓ 18.975	✓ 13.92	1320.66	Rupees One Thousand Three Hundred Twenty Paise SixtySix Only
24.02	Beyond 10 km upto 20 km per km	MT	✓ 18.975	✓ 11.63	2206.79	Rupees Two Thousand Two Hundred Six Paise SeventyNine Only
Total:-					10477435.66	
				Less(-) 24.01%	2515632.00	
G.Total:-					7961803.66	
Say:-					79.618 lacs	

Rates and quantity checked

Head Draftsman

Terms Conditions:-

- The cost of work in no case exceed beyond Rs 79.618 lacs (Rupees Seventy Nine lacs sixty One Thousand and Forty Seven Thousand and Eight Hundred only)
- Bid declaration security @ 3% vide CDR with Cust ID: 276954615 Dated:-21.11.2024 for an amount of Rs 2,50,000/- is being
- Deposit of the subjected work shall be released after the DLP Period is over i.e (18 Months).
- Contractors are directed to get the 3rd party inspection of pipe material (HDPE) done preferably from M/S Tata Consultancy or Crown Agents India apart from third party inspection agencies already notified in their respective eNITs. (ADVISORY NO: CE/JSD/PS/35727-60 Dated: 20-01-2024)
- The work shall have to be started by you at site immediately and ensure its successful completion within a period of (30 days) as mentioned in e-NIT from the date of issuance of LOI/Allotment from this office strictly in accordance with the approved proposals falling which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be recommended for forfeiting.