

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email: urihydraulic@gmail.com

Allotment Order No. 128 of 10/2023

M/S : Mumtaz Ahamd Khan
S/O : Ghulam Hyder Khan
R/O : Lachipora Tehsil Boniyar
Registration No. : 1154/BK/SE-PWD/DEE/2009-2010
TIN No./GST No:- : 01CZPPK1825F2ZL

Name of work : Construction of Water Supply Scheme Chotali Symali by way of Construction/Commissioning and Testing of SRs /Intake Chambers Chain Link Fencing (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-E)

eNIT No. : 01 /Hyd/Uri of 2023-24 TENDER ID 2023_IFC_209185_54

Your Tender Received in response to : eNIT No:01/Hyd/Uri_of_2023-24 Dated: 03/04/2023 issued under endorsement No:- HDU/CC-02/11-21 Dated: 03/04/2023 (S. No: 54) Tender ID : 2023_IFC_209185_54

Reference :

(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.

(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.

(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.

(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.

(viii) This Office Letter No: HDU/CC-02/3134-35 Dated:- 01/08/2023 and (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/5037-50 Dated:- 04/08/2023

Ref: to AAA : Accorded vide Order No. 45/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2023

Ref: to Tech. Sanction : Accorded vide Order No. CE/PHE/DB/552 of 09/2022 Dated:- 10/09/2022

LOI Issued under No:- : NIT No. 01/3298-99 Dated:- 08/08/2023

Advertisement cost : Rs: 14.90Lacs

Allotted cost : ₹ 1566309.08 Rupees Fifteen Lakh(s) Sixty Six Thousand Three Hundred Nine And Paise Eight Only

Time of completion : 90-days

M.H. of Account : (JJM)

Ref. To CDR/FDR :


Ref. To Additional FDR No. :

Name of the Bank :

BSDF

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"



Terms and Conditions:-

- 1 Time of completion is essence of the contract.
- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depoition of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.
- 14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Checked by**Head Engineer****NO: HDU/CC-04****DATED: 21-10-2023****Copy to the:**

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/5037-50 Dated:- 04/08/2023.
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla(Member DJJM) for information.
- 9 Chief Medical Officer Baramulla(Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.

**Executive Engineer
Hydraulic Division Uri**

Rajesh Shafat

Annexure "A" to the Allotment Order No. 128 of 10/2023

Construction of Water Supply Scheme Chotali Symali by way of Construction/Commissioning and Testing of SRs /Intake Chambers Chain Link Fencing (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-E)

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5m in width, as well as 10Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtr as directed by the Engineer Incharge				
1.1	In all kinds of soils	85.170	Cum	571.711	48692.63
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	12.220	Cum	210.622	2573.80
3	Providing and laying stone soling 2nd class	12.830	Cum	653.384	8382.92
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work up to plinth level with 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size)	8.040	Cum	5153.545	41434.50
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level) with 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	29.880	Cum	6853.107	204770.83
6	Providing and laying in position specified grade of reinforced cement concrete including cuiring but excluding the cost of centering shuttering, finishing and reinforcement (all work upto plinth level l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	6.306	Cum	8268.806	52143.09
7	Reinforced Cement concrete work in wall (any Thickness) including attached Pilasters buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts. upto floor five level incluing curring but excluding cost of centering shuttering, finishing and reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	9.930	Cum	9972.623	99028.15
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, staircases and spiral staircases upto floor five level including curring but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	1.469	Cum	10440.306	15336.81
9	Reinforced cement concrete work in arches, archribs, vaults Shells folded plates and roofs having slope more than 15° upto floor five level including curing but excluding cost of centering and shuttering, finshing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	1.010	Cum	11028.786	11139.07
10	Centering and shuttering including strutting propping etc. and removal of Form for Work for.			0.000	0.00
10.1	Foundations, footings, bases of columns etc.	138.560	Sqm	278.038	38524.95

212
mm
S

S#	Particulars	Qty	Unit	Rate	Amount
10.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	118.030	Sqm	608.281	71795.41
10.3	Suspended floors, roofs, landings, balconies and access platform.	11.320	Sqm	673.736	7626.69
10.6	Arches, Domes, vaults upto 6-mtr span	10.110	Sqm	2212.008	22363.40
11	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	116.350	Sqm	379.480	44152.50
12	Providing and fixing 4mm dia-G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-Incharge	147.400	sqm	777.510	114604.97
13	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturers specification (1-Kg of Water Proofing material in 50-Kgs of cement)	400.000	Kg	71.656	28662.40
14	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1092.770	kg	96.487	105437.55
15	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete.	586.800	kg	113.420	66554.86
16	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	350.220	Kg	108.268	37917.76
17	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete above plinth level TMT Bars.	1646.480	Kg	92.400	152135.08
18	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	165.870	Kg	108.268	17958.48
19	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
19.1	40mm dia	2.000	Nos	3710.000	7420.00
20	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality			0.000	0.00
20.1	50mm dia	6.000	Nos	530.000	3180.00
21	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
21.1	Cement and Steel (55-Kms)	22.350	Mton	706.766	15796.21
21.2	Sand. (60Kms)	25.773	Cum	847.714	21848.13
21.3	Agg. 20mm (80Kms)	41.210	Cum	1058.357	43614.89
21.4	Agg. 40mm (80Kms)	6.770	Cum	1150.323	7787.68
21.5	Stone Soling (07-Kms)	12.830	Cum	294.362	3776.66

21/12/2021

S#	Particulars	Qty	Unit	Rate	Amount
22	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc. Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
22.1	Cement (3000Mtrs)	18.250	Mton	1244.355	22709.48
22.2	Steel (3000Mtrs)	3.781	Mton	2673.108	10107.02
22.3	Sand. (3000Mtrs)	25.773	Cum	3080.572	79395.58
22.4	Agg. 20mm (3000Mtrs)	41.210	Cum	3080.636	126952.99
22.5	Agg. 40mm (3000Mtrs)	6.770	Cum	3330.255	22545.83
22.6	Stone Soling (500Mtrs)	12.830	Cum	774.650	9938.76
				Total	1566309.08

Rupees Fifteen Lakh(s) Sixty Six Thousand Three Hundred Nine And Paise Eight Only

Checked by

Head

Executive Engineer
Hydraulic Division Uri