

GOVT. OF UT JAMMU & KASHMIR
OFFICE OF EXECUTIVE ENGINEER JSD DIVISION HANDWARA



M/S : Ab Majeed Reshi
S/o : Ghulam Ahmad Reshi
R/o : Manzhar Hayama
Regd No : 789/AAAY/CE/KCC/PDC/2007-08
GST No. : 01A0FPR1918B1ZJ

No: - PIIE/land/ 932-35 Date: 19, 6, 2023

Adv. Cost : - Rs 60.15 Lacs
Allotted Cost:-Rs.6255949.92/-
Time of Completion 80 days

Sub : Construction incl. successful testing and commissioning of PST, RCC jacketing of SR, Chain Link fencing and collection chamber for WSS Check Sarmarg under JJM.

Ref:- Your tender in response to this office E-NIT No.04 /PHE /Hand of S.No.11 issued under this Office No.281-91 of 24-04-2023.

2. District Development Commissioner Kupwara's authorization No. DDCK/Plg/MoM/1125-35 dated. 30-05-2023

3. Accord No.CE/PHE/DB/JJM/246 of 08/2022 Dtd. 31-08-2022.

4. Technical Sanction Order No.CE/PHE/DB/233 of 08/2022 Dtd. 31-08-2022.

For and on behalf of Governor of Jammu & Kashmir UT State, contract for the above subjected work, is here by fixed with you on the negotiated / following rates, terms and conditions which are reproduced as under:

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Alloted Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed in:-All kinds of Soil	✓ 11.02	Cum	✓ 436.00	✓ 4804.72
2	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil :	✓ 64.80	Cum	✓ 539.35	✓ 34949.88
3	Earth work in bulk excavation by mechanical means (hydraulic excavator) over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. in all kinds of Soil	✓ 172.00	Cum	✓ 188.75	✓ 32465.00
4	Providing and laying dry stone soling hand packed tightly including Filling, Spreading, ramming cost of Stone boulders and all carriages by MT and H/Load with all leads and lifts complete.	✓ 37.88	Cum	✓ 1320.00	✓ 50001.60

\$
HID
Kew

5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 mix (1 Cement: 4 Course Sand : 8 graded crushed stone agg 40mm nominal size)	25.92	Cum	4861.84	126018.8
6	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 mix (1 Cement: 3 Course Sand : 6 graded crushed stone agg 20mm nominal size)	54.00	Cum	5399.02	291547.08
7	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 mix (1 Cement: 2 Course Sand : 4 graded crushed stone agg 20mm nominal size)	18.03	Cum	6465.20	116567.56
8	Providing and laying in position Reinforced cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:1.5:3 mix (1 Cement: 3 Course Sand : 3 graded crushed stone agg 20mm nominal size)	37.45	Cum	7801.00	292147.45
9	Reinforced cement concrete work in walls (any thickness) including attached pillars, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1.5:3 mix.	64.58	Cum	9408.14	607577.68
10	Reinforced cement concrete work in Suspended floors, roofs having slope upto 15°, beams etc upto floor five level including curing but excluding the cost of centering, shuttering finishing and reinforcement with: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	2.78	Cum	9849.35	27381.19
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level	12246.00	Kg	87.18	1067606.28
12	Providing and incorporating P.G.I sheet strips during lying of concrete walls 0.80mm thick.	53.11	Sqm	800.00	42488.00

WSS Sarmarg Krumhoora under JJM

13	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	779.00 ✓	Kg	57.90	45104.10 ✓
14	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer	59.00 ✓	RM	190.19	11221.21 ✓
15	Centering and shuttering including strutting, propping etc. and removal of form for Foundations	117.33	Sqm ✓	262.30 ✓	30775.66 ✓
16	Walls	811.20 ✓	Sqm	573.85 ✓	465507.12 ✓
17	Extra for Centering Shuttering in Circular Walls	200.75 ✓	Sqm	114.77 ✓	23040.08 ✓
18	12 mm thick Cement plaster 1 : 3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement	249.91	Sqm	343.75	85906.56 ✓
19	12 mm thick Cement plaster 1 : 4 (1 cement : 4 coarse sand) finished with a floating coat of neat cement	285.90 ✓	Sqm	260.05 ✓	74348.30 ✓
20	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel as required In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete.	3038.00 ✓	Kg	114.67 ✓	348367.46 ✓
21	Structural Steel Work in built up sections in trusses, and framed work, including cutting, hoisting, fixing in position and applying a priming coat coat of approved steel primer all complete. (Riveted and bolted)	4185.00 ✓	Kg	105.76 ✓	442605.60 ✓
22	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel as required in gratings, frames, guard bars, ladder, railings, brackets, gates and similar works.	8520.00 ✓	Kg	146.63 ✓	1249287.60 ✓

Handwritten signature and initials

23	Providing and fixing G.I. Chain Link fabric fencing of required width in mesh size 50 x 50mm including strengthening with 2mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer - In- Charge made of G.I. Wire of dia 4mm.	320.58 ✓	Sqm	806.85 ✓	258659 ✓
24	Providing and fixing of sign board over entrance gates incl. painting/writing, cost of fixing at SR site site complete job	5.00 ✓	Sqm	3000.00 ✓	15000.00 ✓
25	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work.	224.41 ✓	Sqm	121.95 ✓	27366.80 ✓
26	Carriage of materials from source to road site of work by Mechanical Transport including loading unloading and stacking complete.				0.00
27	Cement and Steel 20 Km's	74.87 ✓	MT	357.64 ✓	26776.51 ✓
28	Sand and 20mm Crushed agg avg 20kms	266.80 ✓	Cum	402.29 ✓	107330.97 ✓
29	Crushed Aggregate 40mm nominal Size 20 Kms	22.06 ✓	Cum	437.30 ✓	9646.84 ✓
30	Carriage of materials from road site upto actual site of work by manual means (Head Load) avg 200 mtrs including loading unloading and stacking complete.				0.00
31	Cement	19.74 ✓	MT	175.08 ✓	3456.08 ✓
32	Steel	0.76 ✓	MT	376.05 ✓	285.80 ✓
	Total				6015336.46 ✓
	Add Contractors Tender Appreciation @ 4% on All items				240613.46 ✓
	G. Total				6255949.92 ✓

Checked by
Head Draftsman

Executive Engineer
PHE Jal Shakti Division Handwara

WSS Sarmarg Krumhoora