

OFFICE OF THE EXECUTIVE ENGINEER SPECIAL PHE JAL SHAKTI DIVISION KULGAM

M/S **Mr Khursheed Ahmad Dar**
S/o **Haji Abdul Ahad Dar**
R/o **Gudder Kulgam**
Regd No **SE-(R&B) SB-B-1273 of 2019-20**
PAN No. **BFRPA0274B**

No:- PHE/Wks/ **2996-99**
Dated: 01/09/2023

Allotment order No **66** of 2023-24
Dated: 09/09/2023

GST:- 01BFRPA0274B2Z6

Name of work: : Laying and Fitting of pipes including installation of FHTC for W.S.S Sangas Kaharote under JJM.

Ref:-1. This office ENIT No **45** of 2022-23 issued vide No PHED/K/4078-89 dated 08/09/2022
2. This office LOI No PHE/K4670-73 dated 03/10/2022

Accord of Administrative No and date	SE/HYD/DB/208 of 2022 dated 27/08/2022
Technical sanction No and date:	SE/HYD/DB/6056-59 DATED 05/09/2022
Advertised amount of work	Rs 36.13 lacs
Alloted amount of work	Rs33.60 lacs
Rupees thirty three lac sixty thousands only	

For and on behalf of Lt.Governor of UT of J&K, the contract for the above work is hereby fixed with you on the following rates quoted/accepted by you on the terms and conditons given as under:

Sl.No	Bidder Name	Quoted /negotiated Percentage	Negotiated/Alloted Amount in Figures and Words	
			Rate	Amount
1	Mr Khursheed Ahmad Dar	-7.03	Rs33.60 lacs	Rupees thirty three lac sixty thousands only

DESCRIPTION OF ITEMS AS PER BOQ

S.No	Description of items	Quantity	Unit	Estimates rate	Total
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides andramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: all kinds of soil 1 metter from cutting edge	3407.300	Cum	436.000	1485582.80
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5	3066.500	Cum	198.700	609313.55




3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) (For restoration of Lanes)	4.000	Cum	6434.010	25736.04
4	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work. 15 mm and 20 mm dia. G.I. pipes	3500.000 ✓	Mtr	20.250	70875.00
5	25 mm and 32 mm dia. G.I. pipes	2000.000 ✓	Mtr	30.650	61300.00
6	40 mm and 50 mm dia. G.I. pipes	4000.000 ✓	Mtr	40.800	163200.00
7	65 mm and 80 mm dia. G.I. pipes	2300.000 ✓	Mtr	73.050	168015.00
8	100 mm dia. G.I. pipes	1600.000 ✓	Mtr	107.700	172320.00
9	Laying in position centrifugally cast (spun) iron S&S or flanged pipes	1254.900	quintal	245.550	308140.70
10	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket 200mm Dia giges	382.000	each	213.000	81366.00
11	150mm Dia pipes	436.000	each	144.700	63089.20
12	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete 25 to 40 mm nominal bore	100.000	each	666.250	66625.00
13	50 to 80 mm nominal bore	8.000	each	1268.250	10146.00
14	Providing and laying D.I. standard specials such as tees, bends, collars, tapers, caps etc. suitable for flanged jointing as per IS : 9523 (as per site requirement) upto 300mm Dia	1.000	Qtls	7823.700	7823.70
15	Providing and fixing D.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately). Confirming to IS:14846 read with latest amendments. 150 mm dia.	2.000	each	20243.000	40486.00
16	200 mm dia.	2.000	each	31698.000	63396.00
17	Restoration of Road Berm Along Pipe alignment to be damaged -1000 mts @ Rs 480/mt	100.000	Mtr	480.000	48000.00
18	Carriage of G.I./D.I pipes below 100mm dia from Stocking yard to the site by mechanical means Skm	37.260	M.T	183.356	6831.84
19	Carriage of G.I./D.I. pipes 100mm dia from Stocking yard to the site by mechanical means Skms	1600.000	Mtr	4.500	7200.00
20	Carriage of G.I./D.I. pipes 150mm dia from Stocking yard to the site by mechanical means Skms	2400.000	Mtr	7.514	18033.60
21	Carriage of G.I./D.I. pipes 200mm dia from Stocking yard to the site by mechanical means Skms	2100.000	Mtr	12.224	25670.40

Q.21
Q.22

22	Carriage of G.I./D.I pipes below 100mm dia from dumping site to actual site of work by manual means ist 50m	37.260	M.T	153.249	5710.06
23	For additional lift beyond 50 m.	37.260	M.T	247.434	9219.39
24	Carriage of G.I./D.I pipes 100mm dia from dumping site to actual site of work by manual means ist 50m	1600.000	Mtr	4.142	6627.20
25	For additional lift beyond 50 m.	1600.000	Mtr	6.686	10697.60
26	Carriage of G.I./D.I pipes 150mm dia from dumping site to actual site of work by manual means ist 50m	2400.000	Mtr	5.836	14006.40
27	For additional lift beyond 50 m.	2400.000	Mtr	9.419	22605.60
28	Carriage of G.I./D.I pipes 200mm dia from dumping site to actual site of work by manual means ist 50m	2100.000	Mtr	7.615	15991.50
29	For additional lift beyond 50 m.	2100.000	Mtr	12.287	25802.70
Total					3613811.28
Deduct 7.03% to Total Cost					254050.93
Total Alloted cost					3359760.35
Say					33.60lacs


HD



Executive Engineer
Spl.PHE JSD Kulgam


Terms and conditions:::

1	The allotted cost of the work is Rs33.60 lacs (Rupees Thirty three lac sixty thousands only) . However the allotted cost should in no case exceed beyond DAP/DPR.
2	The work shall have to be completed within a period of (30) days from the date of issuance of this allotment order, failing which penalty upto 10% of the total value shall be imposed upon you.
3	Earnest money deposited by you Vide CDR No 3370623 Dated 22/09/2022 For Rs40000.00 and Rs3560882 dated 01/09/2023 for Rs68400.00 issued by JK Bank Branch tarigam and main Kulgam and shall be released only after the successful completion of work and after the expiry of defect clause.
4	The date of start of work shall be reckoned within one week from the date of issuance of this Contract allotment
6	After testing and commissioning of work the bidder will have to make a trial run of the work for a period of 03 months during which the bidder will have to operate and maintain the executed work to the full satisfaction of the Department. the DLP. In case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time as deemed fit for getting the defect rectified subject to maximum ceiling of 06 months
7	The defects Liability period shall be for a period of 12 Months which shall commence after the successful completion of Trai run The bidder shall be responsible to make good & remedy at his own expense any defect in works which is noticed during the DLP in case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time The bidder shall be responsible for the time and proper setting out of all the works and for the correctness of the positions levels dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in as deemed for getting the defect rectified subject to a maximum ceiling of 6 Months
8	The rates are including the Charges for Submission of progress Geo-tagged photographs, vedigraphic record through the professional person before during & after construction and progress reports in both hard and soft copies Taking Cross-Sections L Sections by Auto Level/ETS before and after execution Preparation of work abatract of executed work, preparation of bills besides the rates quoted/alloted are inclusive of taxes and the tees viz GST/income tax/Cess etc shall be deducted at source from running account bills.

9	All the Cement RCC Steel plumbing and other works shall be strictly as per relevant IS Codes CPHEEO norms/requirements/specifications and normal PWD precautions
10	You shall be solely responsible for carrying out the mandatory tests required or as decided by Engineer-in-charge for the quality control at your own costs. The cost of conducting all tests shall be done by the contractor and shall be deemed to have been included in the term rates for various items of work and percentage rate tendered Nothing extra shall be payable on this account
11	You have to furnish the confirmatory survey, structural & functional design including geo-technical analysis, soil investigation and quality control tests done at your level duly vetted by DIGC as per terms & conditions of the NIT The vetting charges for the design if any are to be done by you
12	The allotted works shall be subject to check by the third party monitoring agency (TPIOM) appointed by the Department. The agency shall check the quality of works executed by the agencies, quality of materials used for construction and quality of machinery nated in each scheme The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluation of the performance of the Contract during the Contract Period
13	Any item of work not included in the BOQ but required for the completion of the work, shall be executed by the contractor, as directed by the Department Such extra item shall be paid at J&K SSR 2020 rates with allotted appreciation /Deprisation of the contractor in case such item does not figure in J&K SSR 2020, the same shall be paid as per the current market rate analysis, to be approved by the competent authority
14	No price escalation will be paid for completion of the work within stipulated time or extended data of completion due to any reason whatsoever
15	No extra claim towards any type of tax, freight etc shall be entertained whatsoever.
16	No mobilisation advance shall be paid
17	Retention money/Security deposit shall be 10% of the contract value. The Security Deposit is to be recovered at the rate of 10% of bi amount from Running Account Bills and shall be released after completion of the defect liability period
18	In the event of allottee falling, declining, neglecting or delaying the supplies/works or in the event of any damage securing or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the timebeing enforce in the UT
19	All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract are the responsibility of the Bidder.
20	Any failure or commission to carry out the provision of the contract shall not give any claim by the department or bidder one against the other if such failure of commission occurs by the ACT OF GOD which shall include all natural calamities such as fires floods earthquake, hurricane, strikes, roits, embargoes or from any political or other reasons beyond the control of the paries including war, or a state of insurgency
21	The bidder shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc
22	From the commencement of the work to the completion thereof the same shall be under the bidders charge The bidder shall be hel responsible for and make good any loss or injuries by fire or other causes/theft and shall hold the Government harmless for any cliams for injures to persons or damage a property happening from any neglect, default, want of proper care and misconduct on the part of the bidder, or any of his employees during the execution of work. The bidder shall be responsible for the compensation if any, to labour under the existing labour laws of the country
23	In the event of the death or insanity or insolvency or imprisonment of the bidder or where the bidder being a partnership or firm becomes dissolved or being corporation goes into liquidation, voluntary or otherwise, the contract may, in the option of the Engineerin charge be terminated by notice in writing posted at the site of the works

24	The damage caused to the work during execution or prior to actual completion of wondhanding over of the project before defect lability period due to any natural calamity human interference, the same shall be got restored and made good by you at your own cost
25	No damage is caused to existing structures like roads, bridges, buildings or other public utilites as a result of construction of this work .Where ever any damage occures to any public/private infrastructure or public utility, the same shall be rectified/made good by you at your own cost
26	Adequate precautions be taken for environment and social protection besides, all safety practices in vogue be strictly adhered to during execution of work
27	No objection certificate from the concerned regulatory authority may also be sought whenever required
28	All other terms & conditions will remain same as laid down in the original NIT SBD GFR-2017/ Procurement Manual 2019/Operational guidelines for JJM


HD


Executive Engineer
SpL.PHE JSD Kulgam

Copy to the
Superintending Engineer Hydraulic Circle Aantnag for favour of
Asstt.Ex.Engineer PHE Sub-Division Kulgam for information
AAO Divisional office for information